

State of Kansas



15-195-01492-00-00

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

3-16-1964
MAR 16 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Albert Schiffner of Forbes Casing Pulling, Inc has this

date requested permission to plug the following described well:

Sunray DX Oil Co.

Mr. Schiffner guarantees payment of the plugging fee.

Operator's full Name: Sunray DX Oil Company,

Complete Address: Box # 729, Great Bend, Kansas.

Lease Name: A. L. Struss Well No. 2

Location: SW-NW-SE Sec. 21 Twp. 11 Rge. (E) (W) 24

County Trego Total Depth 4132 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Schiffner was instructed to plug the well as follows:

229'--8 5/8" Surface pipe, cement circulated with 200 Sx.
4131'--5 1/2" production casing cemented on bottom with 150 Sx.
DV Tool @ 2092' circulated with 90 Bbl. oil & 270 Sx. gel.
Well plugged back to 4097'. Top of perforations @ 4026'.
Sand well back to 4015' and set 5 Sx. cement with dump bailer.
pull 5 1/2" to 600' and circulate heavy gel mud and displace 20 Sx.
cement thru 5 1/2". Pull 5 1/2" to 210' and displace 30 Sx. cement
thru 5 1/2". Pull 5 1/2", set bridge @ 30' and 15 Sx. to ground.

Very truly yours,

W. L. Nichols