



15-195-20148-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
12-22-1969
DEC 22 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. John Armbruster of B & B Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Armbruster guarantees payment of the plugging fee.

Operator's full Name: Mid-America Exploration, Incorporated,

Complete Address: Box #302, Chamberlain, South Dakota.

Lease Name: Malinowsky Well No. 1

Location: CSW-SW Sec. 21 Twp. 11 Rge. (E)(W) 24

County: Trego Total Depth 4110' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Armbruster was instructed to plug the well as follows:

208'--8 5/8" Surface casing, cement circulated with 145 Sx.
Top of Dakota section @ 925'.

Circulate hole with heavy mud. Pull DP to 1150' and displace 100 Sx,
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10' Sx. cement to bottom
of cellar.

Very truly yours,

H. L. Nichols
Conservation Division Agent