

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: TGT Petroleum Corp  
Address: 7570 W 21st, Bldg 1010-D, Wichita, KS 67205  
Phone: (316) 773-2266 Operator License #: 5118  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Jeff Klock (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-155-20210-00-00  
Lease Name: Sabin "A"  
Well Number: 2  
Spot Location (QQQQ): NE - SW - NW - NW  
840 Feet from  North /  South Section Line  
580 Feet from  East /  West Section Line  
Sec. 22 Twp. 23 S. R. 4  East  West  
County: Reno  
Date Well Completed: 02-27-73  
Plugging Commenced: 03-23-09  
Plugging Completed: 03-25-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	640	
				5 1/2	3347	2430

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 3270', bailed 5 sacks cement with bailer, pulled slips, ripped casing at 2430', worked pipe free, pulled casing up to 690', pumped 50 sacks cement, pulled casing up to 440', let set for 2 hrs, tagged cement at 515', pulled casing up to 275', pumped 125 sacks to surface, pulled rest of casing, cleaned up location.

KANSAS CORPORATION COMMISSION

APR 15 2009

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925  
Address: 190 US Highway 56, Ellinwood, KS 67526  
Name of Party Responsible for Plugging Fees: TGT Petroleum Corp  
State of Kansas County, Sedgwick, ss.

CONSERVATION DIVISION  
WICHITA, KS

B. Lynn Herrington (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) B. Lynn Herrington  
(Address) 7570 W. 21st, Bldg 1010-D, Wichita, KS 67205

SUBSCRIBED and SWORN TO before me this 10th day of April, 2009  
Nancy K. Bell My Commission Expires: 1/14/2013  
Notary Public

PK

# QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025  
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 2337

Date	3-25-09	Sec.	22	Twp.	23	Range	4	Called Out		On Location		Job Start		Finish	1:00 P.M.	
Lease	SABIN	Well No.	A	Z		Location	HUTCHINSON, KS.			PERO County		State	KS.			
Contractor	Quality Well Service				Owner	9E-1N-1W-1N10										
Type Job	PTA				To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.											
Hole Size					T.D.											
Csg.	5 1/2				Depth	3340										
Tbg. Size					Depth											
Drill Pipe					Depth											
Tool					Depth											
Cement Left in Csg.					Shoe Joint											
Press Max.					Minimum											
Meas Line					Displace											
Perf.						CEMENT USED 175 SK										
EQUIPMENT					Amount Ordered	200 SK Common										
Pumptrk	5	No.	Cementer	Helper	JOE											
Bulktrk	B	No.	Driver	Driver	BOBBY											
Bulktrk	PV	No.	Driver	Driver	TODD											
JOB SERVICES & REMARKS					Gel.											
Pumptrk Charge	PTA				600 <sup>00</sup>	Chloride	1 @ 42 <sup>00</sup>									
Mileage	70' @ 6 <sup>00</sup>					Hulls										
Footage						Salt										
Total					Flowseal											
Remarks:					690' 50 SK Common 3 3/4 CC MIX Pump 50 SK 3 3/4 CC + DESP Pull csg WOC TAG OUT 565'											
270'					MIX Pump 125 SK Common											
CIRC CONT TO SURFACE					Rotating Head											
Thanks TODD JOE BOBBY Signature: TODD ASBRO					PLEASE CALL AGAIN											
					Handling	176 @ 1 <sup>75</sup>										
					Mileage	.08 PER SK PER MILE										
					47 miles	500 <sup>00</sup>										
					Sub Total											
					Total											
					Floating Equipment & Plugs											
					Squeeze Manifold											
					Tax											
					20% Discount											
					Total Charge											

RECEIVED  
KANSAS CONSERVATION COMMISSION  
APR 15 2009  
CONSERVATION DIVISION  
WICHITA, KS

