

APR 15 2009

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

CONSERVATION DIVISION
WICHITA, KS

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5030
Name: VESS OIL CORPORATION
Address 1: 1700 Waterfront Parkway
Address 2: Bldg. 500
City: Wichita State: KS Zip: 67206 + _____
Contact Person: W.R. Horgan
Phone: (316) 682-1537 X102
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Toronto Depth to Top: 3429 Bottom: 3431 T.D. _____
LKC Depth to Top: 3485 Bottom: 3683 T.D. 3785
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. ~~4~~ 15-051-21301 - 0000
Spot Description: _____
_____NW NE SE Sec. 19 Twp. 12 S. R. 18 East West **KCC**
2,310 Feet from North / South Line of Section **PKR**
990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis
Lease Name: Crathorne Well #: 1
Date Well Completed: _____
The plugging proposal was approved on: 3/1/09 (Date)
by: Richard Williams (KCC District Agent's Name)
Plugging Commenced: 3/17/09
Plugging Completed: 3/17/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8-5/8	225	
			4-1/2	3783	
			squeezed	1150	40 sx

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

MIRU. TIH w/workstring to 3270'. Spotted 100 sx 60/40 poz w/4% gel. Pulled tubing to 1750' and circulated cement to surface with 100 sx same cement w/400# hulls. TOH with tubing. Connected to 4 1/2" casing and pumped 25 sx same cement at 300#. SIP - 300#. Connected to 8 5/8" braden head and pumped 50 sx same cement with 100# hulls - 100#. Approved by Rich Williams w/KCC.

Plugging Contractor License #: 5822 99996 **KCC PKR** Name: Allied Cement Co., Inc.
Address 1: P.O. Box 31 Address 2: _____
City: Russell State: KS Zip: 67665 + 0031
Phone: (785) 483-2627
Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Sedgwick, ss.
Patrick T. Canaday (Print Name) Employee of Operator or Operator on above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: [Signature]

15-135'E CN/2 NE SE

42

KANSAS ENERGY EXCHANGE, INC.
1540 NO. BROADWAY, SUITE 205F

#1 CRATHORNE

19-12-18W
NW NE SE

WICHITA, KS.

CONTR BERGMAN DRLG. CO.

CTY ELLIS

GEOL

FIELD HYACINTH

E 2175 KB CM 3/21/77 CARD ISSUED 3/30/78 IP OIL WELL

API 15-051-21,301

LS 2173 DF

INTERVAL NOT
RELEASED

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
GR HAV	2880	- 705	
DOVER LS	2947	- 772	
TARK	2982	- 807	
ELM LS	3032	- 857	
TOP	3173	- 998	
HEEB	3406	-1231	
LANS	3452	-1277	
BKC	3694	-1519	
CONG SD	3736	-1561	
RTD	3785	-1610	

8-5/8" 225/160sx, 4 1/2" 3783/150sx
 DST (1) 3354-3385/30-30-30-30, 110' MSW
 W/FSO, SIP 1213-1213#, FP 64-103#
 (2) 3413-3440/30-30-30-30, 10'M, Tol
 SIP 38-38#, FP 38-38#
 DST (3) 3471-3490/30-30-30-30, 60' HOCH WLL
 430' FO, 120' OCW, 190'SW, SIP
 1123-1084#, FP 103-297#
 DST (4) 3574-3600/30-30-30-30, 540'M WLL
 W/SP O, SIP 774-772#, FP NA
 (MIS-RUN)
 MICT - CO & TSTD - WELL IS POP

VCC

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

RECEIVED
KANSAS CORPORATION COMMISSION

APR 15 2009

CONSERVATION DIVISION
WICHITA, KS

