

APR 15 2009

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

CONSERVATION DIVISION  
WICHITA, KS

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

Lease Operator: R.P. Nixon Operations, Inc.  
Address: 207 W. 12th St., Hays, KS 67601  
Phone: (785) 628-3834 Operator License #: 5252  
Type of Well: D & A Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)* *(If SWD or ENHR)*  
The plugging proposal was approved on: 4-3-2009 (Date)  
by: Rich Williams (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-163-23,793-0000  
Lease Name: Hilgers  
Well Number: 6  
Spot Location (QQQQ): \_\_\_\_\_ - NE - SW - SE  
990 Feet from  North /  South Section Line  
1,650 Feet from  East /  West Section Line  
Sec. 32 Twp. 9 S. R. 17  East  West  
County: Rooks  
Date Well Completed: 4-2-2009  
Plugging Commenced: 4-3-2009  
Plugging Completed: 4-3-2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	219'	Cmtd. w/150 sax

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run drill pipe to 1,384', pump 25 sax cement thru drill pipe; run drill pipe to 850', pump 100 sax cement thru drill pipe; run drill pipe to 270', pump 40 sax cement thru drill pipe; push wiper plug to 40', dump 10 sax cement on plug to cellar. Circulate 30 sax cement down rat hole and 15 sax cement down mouse hole.

Name of Plugging Contractor: Shields Oil Producers Inc Drilling Co. License #: 5184  
Address: PO Box 709, Russell, KS 67665

Name of Party Responsible for Plugging Fees: R.P. Nixon Operations, Inc.

State of KANSAS County, RUSSELL, ss.

Burton Beery Contractor  
(Employee of Operator) or (Operator)


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Burton Beery  
(Address) PO BOX 709, RUSSELL, KS 67665

SUBSCRIBED and SWORN TO before me this 14<sup>th</sup> day of April, 20 09

Keith Phillips  
Notary Public

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*[Handwritten initials]*




# Shields

Russell, Kansas

## WELL LOG

Operator: R.P. Nixon Operations, Inc.  
 Well: Hilgers #6  
 Commenced: 3-26-2009  
 Completed: 4-3-2009  
 Contractor: Shields Drilling Co.

Well Description: 990' FSL, 1,650' FEL  
 SE/4 Sec. 32-9S-17W  
 Rooks Co., KS



Elevation: 2,110' KB

Treatment:

Production: D & A

Tops:

### CASING RECORD

Size	Run	Pulled
8 5/8"	219'	Cmtd. w/150 sax

..... Figures Indicate Bottom of Formations .....

Sand & shale	825'
Sand	1,105'
Sand & redbed	1,366'
Anhydrite	1,402'
Redbed & shale	1,995'
Shale	2,745'
Shale & lime	3,395'
Lime	3,575' RTD

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 15 2009

CONSERVATION DIVISION  
WICHITA, KS

Notes