

Do not fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 4787
Name: TDI, Inc.
Address 1: 1310 Bison Road
Address 2: _____
City: Hays State: KS Zip: 67601 + _____
Contact Person: Tom Denning
Phone: (785) 628-2593
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Kansas City Depth to Top: 3100' Bottom: 3338' T.D. _____
Arbuckle Depth to Top: 3362' Bottom: 3393' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 051-21635 - 0000
Spot Description: _____
C S/2 S/2 NE/4 Sec. 21 Twp. 14 S. R. 16 East West
2,310 Feet from North / South Line of Section
1,320 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis
Lease Name: Dreiling A (D) Well #: 5
Date Well Completed: 02/05/1979
The plugging proposal was approved on: 03/23/2009 (Date)
by: Case Morris (KCC District Agent's Name)
Plugging Commenced: 03/25/2009
Plugging Completed: 03/25/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		surface	8 5/8"	208'	none
		production	5 1/2"	3375'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tubing to 3300'. Pump 5 bbls of fresh water. Mix 15 sxs of gel. Mix 50 sxs 60/40 w/ 4% gel and 300# of cotton seed hulls. Displace with 8 bbls of water. Pull tubing to 1250'. Mix 150 sxs 60/40 w/ 4% gel and 200# of cotton seed hulls. Circulate to surface. Hook up to the backside and pump in 2 bbls.

RECEIVED
KANSAS CORPORATION COMMISSION
APR 14 2009
6426
CONSERVATION DIVISION
WICHITA KS

KCCPRT Per CP-13
Express Well Service & Supply
Inc

Plugging Contractor License #: _____ Name: Allied Cementing Co., LLC
Address 1: PO Box 31 Address 2: _____
City: Russell State: Kansas Zip: 67665 + _____
Phone: (785) 483-2627
Name of Party Responsible for Plugging Fees: TDI, Inc.
State of Kansas County, Ellis, ss.
Tom Denning, President of TDI, Inc Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Signature]

[Signature]

ALLIED CEMENTING CO., LLC. 036284

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Great Bend
~~Russell~~ KS

DATE <u>8-25-09</u>	SEC. <u>21</u>	TWP. <u>17</u>	RANGE <u>16</u>	CALLED OUT <u>600 AM</u>	ON LOCATION <u>900 AM</u>	JOB START <u>9:30 AM</u>	JOB FINISH <u>11:30 AM</u>
LEASE <u>Drilling</u>	WELL # <u>5</u>	LOCATION <u>walkers ks 25outh</u>				COUNTY <u>Ellis</u>	STATE <u>KS</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)		<u>1 west 1/2 south west in TD</u>					

CONTRACTOR Express

TYPE OF JOB old hole Plus

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2 DEPTH _____

TUBING SIZE 2 3/4 DEPTH 3000

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX 900 MINIMUM 0

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT 9 88hs

EQUIPMENT _____

PUMP TRUCK CEMENTER Ever
warne-D

366 HELPER Carl-D

BULK TRUCK _____

378 DRIVER Chris

BULK TRUCK _____

_____ DRIVER _____

OWNER ~~Express~~ TDI

CEMENT

AMOUNT ORDERED 200 sx 60/40/4% Gel
15 sx Gel on side
500# cotton seed hulls
used 1955x 60/40/4%

COMMON	<u>115</u>	@	<u>13.50</u>	<u>1552.50</u>
POZMIX	<u>80</u>	@	<u>7.55</u>	<u>604.00</u>
GEL	<u>19</u>	@	<u>20.25</u>	<u>384.75</u>
CHLORIDE		@		
ASC		@		
	<u>500 Hulls</u>	@	<u>31.05</u>	<u>15525</u>
		@		
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>224</u>	@	<u>225.00</u>	<u>504.00</u>
MILEAGE	<u>17/229/10</u>			<u>380.80</u>
TOTAL				<u>3581.30</u>

REMARKS:

588hs fresh water ahead
Mix 155x Gel mix 505x 60/40 4%
Gel 300# cotton seed hulls
Displace 88hs of water
2nd Plug 1250 Mix 180 5x 60/40/4% Gel
200# Cotton seed hulls To Surface
188hs Displacement Hook up To back side
Pump 288hs Down casing 388hs
wash up ris Down

SERVICE

DEPTH OF JOB 3000

PUMP TRUCK CHARGE 875.00

EXTRA FOOTAGE @ _____

MILEAGE 17 @ 119.00

MANIFOLD @ _____

TOTAL 994.00

CHARGE TO: ~~Express~~ TDI

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
TOTAL _____		

RECEIVED
KANSAS CORPORATION COMMISSION
APR 14 2009
CONSERVATION DIVISION
WICHITA, KS

To Allied Cementing Co., LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME [Signature]

SIGNATURE _____

SALES TAX (If Any) _____

TOTAL CHARGES [Signature]

DISCOUNT _____ IF PAID IN 30 DAYS _____