

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 9855
Name: Grand Mesa Operating Company
Address 1: 1700 N. Waterfront Pkwy, Bldg 600
Address 2: _____
City: Wichita State: KS Zip: 67206 + 5 5 1 4
Contact Person: Ronald N. Sinclair
Phone: (316) 265-3000
Type of Well: (Check one) Oil Well Gas Well OG ~~OG~~ Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
N/A Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 155-21497-00-00
Spot Description: 1400' FNL & 580' FEL
_____ E/2 NE Sec. 10 Twp. 23 S. R. 10 East West
1,400 Feet from North / South Line of Section
580 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Reno
Lease Name: Keesling Well #: 1-10
Date Well Completed: 01/04/06
The plugging proposal was approved on: 3/18/09 (Date)
by: Jeff Klock-Dist #2 (KCC District Agent's Name)
Plugging Commenced: 03/18/09
Plugging Completed: 03/19/09

CP 2/13

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface, Conductor & Production) | | | |
|---------------------------|---------|-------------------------------------------------|--------|---------------|------------|
| Formation | Content | Casing | Size | Setting Depth | Pulled Out |
| | | Surface | 8 5/8" | 220' | -0- |
| | | Production | 5 1/2" | 3790' | 1540' |
| | | | | | |
| | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tagged cement @ 3740', dug cellar, unpacked casing head, loaded hole with water, set floor, pulled slips, had 15" stretch. Ripped casing @ 2800', 2600', 2400', 2200', 2000', 1800', 1600', 1540', came loose @ 1540', pulled up to 1400', pumped 35sxs of 60/40 pozmix, 4% Gel and 100# hulls, pulled to 900'. Pumped 35sxs 60/40 pozmix, 4% gel and 100# hulls, pulled to 270', pumped 120sxs to surface, pulled rest of casing, tore down floor and rig, emptied pit, cleaned up location.

KANSAS CORPORATION COMMISSION
APR 16 2009
CONSERVATION DIVISION
WICHITA, KS

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc.
Address 1: 190 U.S. Highway 56 Address 2: _____
City: Ellinwood State: Kansas Zip: 67526 + _____
Phone: (785) 483-2025
Name of Party Responsible for Plugging Fees: Grand Mesa Operating Company
State of Kansas County, Sedgwick, ss.
Ronald N. Sinclair, President Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Ronald N. Sinclair

RKT