

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32693
Name: Hawkins Oil LLC.
Address 1: 427 S Boston Ave.
Address 2: Suite #915
City: Tulsa State: OK Zip: 74103 +
Contact Person: J. Hunt Hawkins
Phone: (918) 382-7743
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 2458 Bottom: 2464 T.D. 2520
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 015-22393 - 00-00
Spot Description: _____
SE/4 SE/4 NE/4 Sec. 6 Twp. 26 S. R. 5 East West
2310 Feet from North / South Line of Section
330 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Butler
Lease Name: Marsh A Well #: 11
Date Well Completed: 8/23/1983
The plugging proposal was approved on: 3/26/2009 (Date)
by: Steven Bond, District #2 (KCC District Agent's Name)
Plugging Commenced: 3/25/09
Plugging Completed: 3/26/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	225'	0
2445' - 2452' & 2458' - 2464'	Oil & Water	Production	4 1/2"	2519'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 2333.95'. Cemented bottom plug across Arbuckle covering open perms from 2458' - 2464' with 35 sx cement. Pulled tubing up to 1748. Waiter 1 hr. tagged top of cement @ 2195'. Pressure test OK. Pulled rest of tubing out. Perforated @ 275' with 4 shots. Swedged off 4 1/2", cemented down 4 1/2" with 126 sx to surface. P&A completed 3/26/09.

KCC PKT

Plugging Contractor License #: 5870 Name: Phillips Well Service Inc
Address 1: PO Box 1263 Address 2: _____
City: El Dorado State: KS Zip: 67042 +
Phone: (316) 321-6650
Name of Party Responsible for Plugging Fees: Hawkins Oil LLC.
State of Tulsa County, Oklahoma, ss.
J. Hunt Hawkins Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: J. Hunt Hawkins

RECEIVED
KANSAS CORPORATION COMMISSION

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

APR 08 2009

CONSERVATION DIVISION
WICHITA, KS