

15-195-21677-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21,677-00

LEASE NAME McINTOSH

WELL NUMBER #1

SPOT LOCATION NE SW NE

SEC. 30 TWP. 11 RGE. 24 (W)

COUNTY Trego

Date Well Completed 2-21-85

Plugging Commenced 2-21-85

Plugging Completed 2-21-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Chief Drilling Co., Inc.

ADDRESS 905 Century Plaza
Wichita, Ks. 67202

PHONE # (316) 262-3791 OPERATORS LICENSE NO. 5886

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6 Dale Balthazore

Is ACO-1 filed? yes If not, is well log attached? on back of ACO-1

Producing formation _____ Depth to top _____ bottom _____ T.D. 4070'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface	8 5/8" new 20#	254'	set @ 262'	cem. w/150	sks. 60-40	posmix 2% gel, 3% c.c.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged w/185 sx. 50-50 posmix, 6% gel, 3% c.c. 1st plug @ 2100'
w/25 sx. 2nd plug @ 1165' w/100 sx., 1 sx. flow seal, 3rd plug @ 270' w/
40 sx., solid bridge @ 40' w/10 sx. 10 sx. in the rat hole, started @ 6:15
a.m. completed @ 8:30 a.m.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Warrior Drilling Co. License No. 5883
Address 905 Century Plaza, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

F.W. Shelton, Jr., (employee of operator) or
operator of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) F.W. Shelton, Jr.
(Address) 905 Century Plaza
Wichita, Ks. 67202

2-27-1985
FEB 27 1985

CONFIRMATION DIVISION
WICHITA, KANSAS

MARTHA E. GUSTIN
NOTARY PUBLIC
STATE OF KANSAS
EXPIRES 4/15/85

AND SWORN TO before me this 26 day of Feb., 1985
Martha E. Gustin
Notary Public
My Commission expires: 4/15/85