

15-195-00123-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Trego County. Sec. 32 Twp. 11 Rge. 24 (~~4~~) (W)

Location as "NE/CNW&SW¼" or footage from lines. SE SE NE

Lease Owner Theodore Gore

Lease Name Schwanbeck Well No. 1

Office Address 400 Brown Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 13, 19 56

Application for plugging filed April 13, 19 56

Application for plugging approved April 16, 19 56

Plugging commenced April 14, 19 56

Plugging completed April 14, 19 56

Reason for abandonment of well or producing formation \_\_\_\_\_

Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4510 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	195	8 5/8"	195	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom plug set at 170' with 1/2 sack hulls, and 15 sacks cement.  
Top plug set at 40' with 1/2 sack hulls and 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
4-24-1956  
APR 24 1956

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company

Address 400 Brown Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

I, Dan J. Kornfeld (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Dan J. Kornfeld, 400 Brown Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of April, 19 56

My commission expires Oct. 21, 1958

[Signature]  
Lucille Harr  
Notary Public.

PLUGGING  
FILE SEC 32 T 11 R 24W  
BOOK 53 LINE 44

15-195-00123-00-00

LOG

Company: Theodore Gore, 400 Brown Building, Wichita 2, Kansas

Contractor: Empire Drilling Company, 400 Brown Building, Wichita 2, Kansas

Farm: Schwanback #1

Location: SE SE NE of Sec. 32-11-24W, Trego County, Kansas

Commenced: March 31, 1956

Elevations: KB 2533'

Completed: April 13, 1956

0 to 195	Clay, sand & Shale
195 to 540	Shale - Shells
540 to 2050	Shale and Sand
2050 to 2128	Shale and Shells
2128 to 2170	Anhydrite
2170 to 2545	Shale and Shells
2545 to 2965	Shale and Lime
2965 to 2970	Shale
2970 to 3050	Shale and Lime
3050 to 3190	Lime and Shale
3190 to 3345	Shale and Lime
3345 to 3445	Lime and Shale
3445 to 3545	Shale and Lime
3545 to 3735	Lime and Shale
3735 to 3860	Shale and Lime
3860 to 3920	Lime and Shale
3920 to 3985	Shale and Lime
3985 to 4030	Lime
4030 to 4150	Lime
4150 to 4205	Lime and Shale
4205 to 4345	Shale
4345 to 4504	Shale and Lime
4504 to 4510	Chert & Lime

TOPS:	
Heebner	3865'
Toronto	3888'
Kansas City	3904'
B.K.C.	4143'
Basal Penn. Conglomerate	4437'
Mississippi	4460'
R.T.D.	4510'
Ran Schlumberger Electric Log	
T.D.	4511'

CASING RECORD: Ran 195 ft. of 8 5/8" and cemented with 115 Sacks cement

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Schwanbeck No. 1, SE SE NE of Sec. 32-11-24W, Trego County, Kansas as reflected by the files of the Empire Drilling Company

*Dan J. Kornfeld*  
Dan J. Kornfeld

Subscribed and sworn to before me, a notary public within and for Sedgwick County, Kansas, this 23rd day of April, 1956.

*Lucille Harr*  
Lucille Harr, Notary Public

My commission expires Oct. 21, 1958.



RECEIVED  
STATE CORPORATION COMMISSION  
4-24-1956  
APR 24 1956  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 32 T 11 R 24W  
BOOK PAGE 53 LINE 44