

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-195-2190-00-00

API NUMBER 15-195-21,901-00-00

LEASE NAME Malinowsky

WELL NUMBER 2

3620 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 33 TWP. 11 RGE. 24 ~~XXXX~~(W)

COUNTY Trego

Date Well Completed 5/5/87

Plugging Commenced 5/5/87

Plugging Completed _____

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR N-B Company, Inc.

ADDRESS P. O. Box 506, Russell, KS 67665-0506

PHONE#(913) 483-5345 OPERATORS LICENSE NO. 6111

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District #6

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4100'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		-0-	220'	8-5/8"	220'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to _____ feet each set.

Mud laden fluid 4100' - 2120'

25 sks cement @ 2120' 10 sks cement @ 40'

100 sks cement @ 1220' 15 sks cement @ Rathole

40 sks cement @ 270' 10 sks cement @ mousehole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]
 Kyle B. Branum

(Address) P. O. Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 13th day of May, 19 87

Glenda R. Tiffin RECEIVED
 STATE CORPORATION COMMISSION

My Commission Expires: February 6, 1988



5-14-1987
 MAY 14
 CONSERVATION DIVISION
 Wichita, Kansas
 Form CP-4
 Revised 07-86

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: N-B Company, Inc.
P. O. Box 506
Russell, KS 67665-0506

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Malinowsky WELL #2

LOCATION: NE SW NE
Section 33-11S-24W
Trego County, Kansas

ROTARY TOTAL DEPTH: 4100'

ELEVATION: 2529' K.B.

COMMENCED: 4/29/87

COMPLETED: 5/5/87

CASING: 8-5/8" @ 220' w/150 sks cement

STATUS: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Sand	40'	Sand	1866'
Sand & Shale	221'	Shale & Sand	2115'
Shale	1070'	Anhydrite	2155'
Sand	1125'	Shale	2605'
Shale	1480'	Shale & Lime	3995'
Shale & Sand	1645'	Lime (R.T.D.)	4100'

STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

Kyle B. Branum

Kyle B. Branum

Subscribed and sworn to before me on May 12, 1987.

My commission expires: February 6, 1988.



RECEIVED
STATE CORPORATION COMMISSION
Glenda R. Tiffin
Glenda R. Tiffin, Notary Public
5-14-1987
CONSERVATION DIVISION
Wichita, Kansas