

15-179-20503-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Hughes

WELL NUMBER #1

_____ Ft. from S Section Line

_____ Ft. from E Section Line
C SW SW

SEC. 22 TWP. 9 RGE. 29W (E) or (W)

COUNTY Sheridan

Date Well Completed 3-6-78

Plugging Commenced 4-5-88

Plugging Completed 4-7-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mustand Drilling & Exploration, Inc.

ADDRESS P.O. Box 1609
Great Bend, Kansas 67530

PHONE# (316) 792-7323 OPERATORS LICENSE NO. 5652

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #6 Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	502'	none
				5-1/2"	4283'	1739'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 4100' and 5 sacks cement. Shot pipe @2610', 2406', 2111', 1807', 1739', pulled a total of 41 joints of 5-1/2" casing. Plugged surface with 25 sacks econolite, 2 sacks hulls and 3 sacks hulls mixed with 175 sacks econolite. Plugging Complete.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss. 4-12-88

R. Darrell Kelso

(Employee of Operator Wichita, Kansas) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso
Box 347

(Address) Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 11th day of April, 1988

Irene Hoover
Notary Public

My Commission Expires:



DRILLER'S LOG

COMPANY: Gulf Energy & Minerals Co. - U.S. SEC. 22 T. 9S R. 29W

LOC. C SW SW

WELL NAME: Archie Hughes No. 1-22

COUNTY: Sheridan

RIG NO. #1

TOTAL DEPTH 4300'

ELEVATION

COMMENCED: 2-22-78

COMPLETED: 3-6-78

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 507' w/300 sx. Class A, 16% gel, 2% cc., 3% NACL and 100 sx. Class A, 2% cc.

PRODUCTION: 5 1/2" @ 4283' w/200 sx. 50/50 poz., 2% gel, 3/4 of 1% CFR2.

LOG

(Figures Indicate Bottom of Formations)

Sand & Shale	300
Shale	707
Sand & Shale	1640
Shale & Sand	1972
Sand & Shale	2719
Shale	3279
Shale & Lime	3730
Lime & Shale	3874
Shale & Lime	3962
Lime & Shale	4134
Shale & Lime	4166
Lime & Shale	4300
<u>ROTARY TOTAL DEPTH</u>	<u>4300</u>

STATE OF Kansas)

COUNTY OF Sedgwick)

SS: