

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-179-20483-0000

API NUMBER _____

LEASE NAME Pratt Heirs

WELL NUMBER P-1

_____ Ft. from S Section Line

_____ Ft. from E Section Line

SEC. 22 TWP. 9S RGE. 29W (E or W)

COUNTY Sheridan

Date Well Completed _____

Plugging Commenced 2-26-92

Plugging Completed 3-2-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market Suite #1000 Wichita, Ks. 67202

PHONE# (316) 267-4375 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4250'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	259'	none
				5 1/2"	4250'	1523'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Sanded bottom to 3920' ran 5 sacks cement. Shot pipe @2500', 2100', 1800', 1600', 1523'. Pulled up to 1400' circulated from 1400' to surface with 250 sacks 65/35 10% gel, 5 hulls.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 16 day of March, 19 92

My Commission Expires: _____



Notary Public

WELL LOG

State Geological Survey
WICHITA BRANCH
SEC. 22 T. 9S R. 29W
LOC. C SW SE

COMPANY Don E. Pratt

FARM TOM PRATT HEIRS NO. 1-22


RIB. NO. 16

TOTAL DEPTH 4250'

CONM. 11/7/77

COMP. 11/16/77

COUNTY Sheridan
KANSAS



CONTRACTOR Murfin Drilling

CASING

20	10
15	8 5/8" @ 259' w/220 SX
12	6
13	5 1/2" @ 4249' w/200 SX

ELEVATION

PRODUCTION Producer

FIGURES INDICATE BOTTOM OF FORMATIONS

surf soil	45
sand	220
shale	259
sand, shale	2311
shale, red bed	2475
shale	3785
shale, lime	4050
shale	4080
lime, shale	4120
shale	4250
RTD	4250

15-179-20483-0000