

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-179-20,114 - 0001

LEASE NAME Welch "P"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 11 TWP. 9 RGE. 28 (E) or (W)

COUNTY Sheridan

Date Well Completed 7-68

Plugging Commenced 12-18-97

Plugging Completed 12-18-97

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS P.O. Box 783188 Wichita, KS 67278-3188

PHONE (316) 691-9500 OPERATORS LICENSE NO. 4767

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 18, 1997 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? _____

Producing Formation L/KC Depth to Top 3834 Bottom 4036 T.D. 4105

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	271'	none
				4 1/2"	4103'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Ran open-ended tbq to 3550'. Pumped 50 sx 60/40 poz, 10% gel, 1/4# sx Flocele & 100# hulls down tbq. Pulled tbq up to 2498', pumped 50 sx w/100# hulls. Pulled tbq up to 1456', pumped 70 sx w/200# hulls. Pulled tbq out of hole. Squeezed csg w/15 sx to 400#, held, shut in. Pumped 65 sx w/100# hulls down 8 5/8" csg. Pressured to 100#, held, shut in. Plugging complete 12:50 p.m.

Name of Plugging Contractor Allied Cementing License No. _____

Address Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

A. Scott Ritchie III (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, STATE OF KANSAS COMMISSION

(Signature) [Signature]
(Address) A. Scott Ritchie III
President

12-29-97
DEC 29 1997
STATE OF KANSAS COMMISSION

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 19 97

WICHITA, KANSAS
NOTARY PUBLIC

[Signature]
Notary Public

JULIE K. STOUT
Notary Public - State of Kansas
My Appt. Expires 7-23-2001

Commission Expires: July 23, 2001