

15-179-2017-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER spud 7/20/68

LEASE NAME Welch "P"

WELL NUMBER #2

2305 Ft. from S Section Line

1655 Ft. from E Section Line

SEC. 11 TWP. 9S RGE. 28 (E) or (W)

COUNTY Sheridan

Date Well Completed 8/15/68

Plugging Commenced 4/22/99

Plugging Completed 4/22/99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS P.O. Box 783188

PHONE#(316) 691-9500 OPERATORS LICENSE NO. 4767

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/22/99 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation Toronto, LKC Depth to Top 3830' Bottom 4042' T.D. 4054' 4106'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Toronto	oil & brine	3830	3830	8 5/8"	271'	- 0 -
LKC	oil & brine	3885	4042	4 1/2"	4102'	- 0 -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perforated 4 1/2" csg @ 2350' (Anhydrite) & 1950' (Base of Dakota) with 2 spf.
Ran 2" tbg to 3357'. Pumped 50sx 60/40 pozmix cement blend down tbg. Pulled
tbg up to 2350'. Pumped 50 sx 60/40 pozmic cement blend down tbg. Pulled tbg
up to 1343'. Pumped 70 sx 60/40 pozmic cement blend down tbg. OVER
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. not required
Address Hays, Kansas 67601-0069

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Sedwick, ss.

A. Scott Ritchie III (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 783188, Wichita, KS 67278



Subscribed AND SWORN TO before me this 10th day of May, 19 99

[Signature]
Notary Public
Andrea Perez

My Commission Expires: January 26, 2002

Circulated cement to surface up 4 1/2" csg. Pulled tbg out of hole. Squeezed 4 1/2" csg with 20 sx 60/40 pozmix cement blend, to 500', held, shut-in. Pumped 50 sx 60/40 pozmix cement blend, down 8 5/8" csg to 100', held, shut-in. Plugging complete at noon, 4/22/99.

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15-179-20117-0006

COMPANY **CHAMPLIN PETROLEUM**

SEC. 11 T. 9 R. 28W

FARM **Helen E. Welch** NO. 2


LOC. NE NW SE

TOTAL DEPTH **4106'**

COUNTY **Sheridan**

COMM. **7-20-68**

COMP. **7-30-68**



SHOT OR TREATED

CONTRACTOR **Gabbert-Jones**

ISSUED **9-28-68**

CASING

20 10 5/8" 271' cem w/225 sx
 15 8
 12 6
 13 5
 4 1/2" 4102' cem w/ 200 sx

ELEVATION **2708' DF**

PRODUCTION **P 125 BOPL, NW
 KC 4014-42 Grav 40,2**

FIGURES INDICATE BOTTOM OF FORMATIONS

0	271	SURFACE CLAY, SHALE AND SHELLS
271	500	SHALE
500	750	SHALE AND SAND
750	1490	SHALE
1490	1610	SHALE AND SHELLS
1610	1950	SHALE
1950	2100	SHALE AND RED BED
2100	2330	SHALE
2330	2365	ANHYDRITE
2365	2700	SHALE AND SAND
2700	2880	SHALE
2880	3850	SHALE AND LIME
3850	4105	LIME
4106	TD	

RAN 8 JOINTS 8-5/8" CASING, SET @ 271' w/225 BAGS CEMENT.

RAN 128 JOINTS 4 1/2" CASING, SET @ 4102' w/200 BAGS CEMENT. PUMPED 135 BARRELS OF MUD PACK THRU STAGE TOOL @ 1820'.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE NE NW SE SECTION 11-9S-28W, SHERIDAN COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. HALL

STATE OF KANSAS)

COUNTY OF SEDGWICK)

SS

TOPS: LOG

Anhydrite	2330
Heebner	3806
Toronto	3830
Lansing	3844
Base Kansas City	4079
RTD	4105
LTD	4106