

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-179 - 20124 - 0006

LEASE NAME Rogers E

WELL NUMBER 2

2970 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 11 TWP. 9 RGE. 18 (E) or (W)

COUNTY Sheridan

Date Well Completed \_\_\_\_\_

Plugging Commenced 2/25/91

Plugging Completed 2/25/91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Sterling Oil Company, Inc.

ADDRESS 112 S. Broadway, Sterling, KS 67579

PHONE# (316) 278-3727 OPERATORS LICENSE NO. 30108

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/20/91 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation L-KC Depth to Top 3812 Bottom 3919 T.D. 4090  
3919 RT

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	288	8 5/8	288-239	none
		0	4079	8 5/8	4079-4089	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet, each set.

Perf 2200' & 1445' pumped 200 sks cmt & 250# hulls

down 5 1/2 csg

Pumped 100 sks cmt down 8 5/8 csg

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor G & L Well Service License No. 08253

Address 612 E. Washington, Sterling, KS 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Sterling Oil Company, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Curt Bennett (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Curt Bennett

(Address) 112 S. Broadway, Sterling, KS 67579

SUBSCRIBED AND SWORN TO before me this 26<sup>th</sup> day of February, 19 91

Connie J. Garrett  
Notary Public

My Commission Expires: 11/15/92



15-179-2024-0000

**KANSAS GEOLOGICAL SOCIETY**  
**KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU**  
**KANSAS GEOLOGICAL SOCIETY BUILDING**  
**508 EAST MURDOCK - WICHITA, KANSAS**

COMPANY **KAISER-FRANCIS OIL PRODUCER**


SEC. 11 T. 9 R. 28W

FARM **Rogers "E"** NO. 2

LOC. **SE SW NE**

TOTAL DEPTH **4090'**  
 COMM. **8-9-68** COMP. **8-18-68**  
 SHOT OR TREATED  
 CONTRACTOR **L. J. Dreiling & Sons**  
 ISSUED **10-19-68**

COUNTY **Sheridan**



**CASING**

20 10  
 15 8 5/8" 239' cem w/ 175 sx  
 12 6  
 13 5 1/2" 4089' cem w/ 200 sx

ELEVATION **2678' KB**

PRODUCTION **PMP 160 BOPD, NW/**  
**Lans 3986 1/2-4015, GR 33.2**

FIGURES INDICATE BOTTOM OF FORMATIONS

0'	20'	Surface Soil
20'	138'	Sand & Clay
138'	239'	Shale
239'	1000'	Shale & Sand
1000'	1700'	Shale & Sand
1700'	1810'	Shale
1810'	1888'	Shale & Gyp
1888'	2298'	Shale & Redbed
2298'	2334'	Anhy.
2334'	2645'	Shale & Shells
2645'	3300'	Shale & Lime
3300'	3610'	Lime
3610'	3745'	Lime, Shale & Chalk
3745'	4090'	Lime
4090'	T.D.	

STATE OF KANSAS)

COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Rogers "E" #2.

*Leo F. Dreiling*  
 LEO F. DREILING

TOPS: LOG

Anhydrite	2300
Topeka	3557
Heebner	3771
Toronto	3797
Lansing	3812
LTD	4037
RTD	4090