


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Sheridan County, Sec. 11 Twp. 9 Rge. 28 (E) W (W)  
Location as "NE/CNW%SW%" or footage from lines SE NW NE  
Lease Owner Herman George Kaiser  
Lease Name Rogers E Well No. 4  
Office Address 909 Palace Bldg., Tulsa, Oklahoma 74100  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 10-15 19 68  
Application for plugging filed 10-15 19 68  
Application for plugging approved 10-15 19 68  
Plugging commenced 10-15 19 68  
Plugging completed 10-15 19 68  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	245'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st. plug was set @ 1395' with 70 sacks cement  
2nd. plug was set @ 245' with 20 sacks cement  
3rd. plug was set @ 40' with 1/2 sack hulls and 10 sacks cement  
Cementing to bottom of cellar



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.  
Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.  
I, Leo F. Dreiling (employee of owner) or (owner) of the above-described

well, being duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling  
LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671  
(Address)

Subscribed and sworn to before me this 17th day of October, 1968



JOSEPH A. HESS Notary Public.

# L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

## WELL LOG

Company	Herman George Kaiser 909 Palace Bldg. Tulsa, Oklahoma 74100	Sec. 11	Twp. 9	Rng. 28
Farm	Rogers E No. 4	Location	SE NW NE	
Total Depth	4060'	County	Sheridan	
Comm.	10-8-68	Comp.	10-15-68	Elevation: 2693' K.B.
Contractor	L. J. Dreiling & Sons, Inc. Victoria, Kansas 67671			2690' D.F.
		Casing Record	Cement Record	2688' G.R.
		245' - 8 5/8"	175 sacks cement	Production: D & A

Figures Indicate Bottom of Formations

0'	40'	Surface Soil & Clay
40'	160'	Sand & Gravel
160'	190'	Shale
190'	245'	Shale
245'	1210'	Shale & Sand
1210'	1660'	Shale & Sand
1660'	1840'	Shale & Gyp
1840'	1884'	Shale & Sand
1884'	1970'	Shale & Gyp
1970'	2110'	Sand
2110'	2322'	Shale
2322'	2355'	Anhy.
2355'	3490'	Lime & Shale
3490'	3677'	Lime
3677'	3740'	Lime Chalky & Shale
3740'	3832'	Lime
3832'	4060'	Lime
4060'	T.D.	

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 21 1968  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS)  
)ss  
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Rogers E #4.

*Leo F. Dreiling*  
\_\_\_\_\_  
LEO F. DREILING

Subscribed and sworn to before me this 17th day of October 1968.

*Joseph A. Hess*  
\_\_\_\_\_  
JOSEPH A. HESS NOTARY PUBLIC



My commission expires: September 19, 1970