

15-179-20115-0000

RECEIVED
STATE CORPORATION COMMISSION
4-9-71
APR 9 1971
CONSERVATION DIVISION Form CP-4
Wichita, Kansas

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Sheridan County. Sec. 12 Twp. 9 Rge. 28 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE NW SW

Lease Owner Dreiling Oil Co., Inc.

Lease Name Lindeman Well No. # 2

Office Address R. R. # 2; Victoria, Kansas 67671

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 1971

Application for plugging filed March 1971

Application for plugging approved March 1971


Plugging commenced March 27 1971

Plugging completed March 31 1971

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 1971

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Bill Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	231	None
				4 1/2	4155	1505

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

March 27, 1971 Plugged off bottom. Dumped sand to 3275'. Mixed and dumped 4 sx of cement to 3225'.

March 31, 1971 Plugged off top. Sun Oil Well Cementing Co. mixed and pumped down 8 5/8" surface casing:
5 sx hulls
5 sx gel
100 sx cement
22 sx gel
25 sx cement
3 sx gel
and 20 sx cement


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor RUSS CASING PULLING, INC.
Address P. O. Box 1082 Great Bend, Kansas 67530

STATE OF _____, COUNTY OF _____, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
R.R. #2, Victoria, Kansas 67671
(Address)



Subscribed and sworn to before me this 8th day of April, 1971

My commission expires 1-13-75
Patty Dreiling
PATTY DREILING Notary Public.

L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

WELL LOG

Company **Leo J. Dreiling Oil Company**
Route 2
Victoria, Kansas 67671

Farm **Lindeman** No. **2**

Total Depth **4155'**

Comm. **7-11-68** Comp. **7-19-68**
L. J. Dreiling & Sons, Inc.

Contractor **Route 2**
Victoria, Kansas 67671

Sec. **12** Twp. **9** Rng. **28**

Location **SE NW SW**

County **Sheridan**

Elevation: **2752'** K.B.
2749' D. F.
2747' G. R.

Casing Record	Cement Record	Production:
231' - 8 5/8"	160 sacks cement	10 bbls Chem. flush, 10 bbls Salt Flush,
4155' - 4 1/2"	200 sacks cement, 50-50 pozmix, 2% gel, 1% calcium, 10% salt	

Figures Indicate Bottom of Formations

0'	40'	Surface Soil & Clay
40'	190'	Sand & Clay
190'	231'	Shale
231'	1882'	Shale
1882'	2352'	Shale & Sand
2352'	2372'	Shale
2372'	2406'	Anhy.
2406'	2590'	Redbed & Shale
2590'	2990'	Shale & Shells
2990'	3095'	Shale
3095'	3640'	Shale & Lime
3640'	3875'	Lime
3875'	3910'	Lime & Shale
3910'	4155'	Lime
4155'	T.D.	

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 17 1971
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Lindeman #2.


Leo F. Dreiling

 LEO F. DREILING

Subscribed and sworn to before me this 22nd. day of July 1968.

Joseph A. Hess

 JOSEPH A. HESS NOTARY PUBLIC



Commission expires: September 19, 1970