

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sheridan County, Sec. 18 Twp. 9 Rge. 36 ^{26 W} (E) XXXX (W)

Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner M. J. Bove
Lease Name Transue "B" Well No. 1
Office Address 754 E. Wichita, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 7 19 63
Application for plugging filed December 7 19 63
Application for plugging approved December 7 19 63
Plugging commenced December 7 19 63
Plugging completed December 7 19 63
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS, Morland, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4061 Feet
Show depth and thickness of all water, oil and gas formations. Schlumberger Log Top

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface - Clay & Sand	- Shale	0	280	8 5/8"	278'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug set at 600' with 20 sacks cement.
Plug set at 260' with 20 sacks cement.
Plug set at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
12-26-63
DEC 26 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company
Address 650 Fourth National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dan J. Kornfeld contractor


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld
650 Fourth Natl. Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of December, 19 63

My commission expires October 21, 1966.

Lucille H. Harr
Notary Public.



LOG

COMPANY: M. J. Bova
 CONTRACTOR: Empire Drilling Company
 FARM: Transue "B" #1
 LOCATION: SW SW NE 18-9-36W, Sheridan County, Kansas
 COMMENCED: November 25, 1963
 COMPLETED: December 7, 1963
 ELEVATION: 2700 KB
 POTENTIAL: D & A

0	to	260	Surface - Clay & Sand
260	to	280	Shale
280	to	1200	Shale & Shells
1200	to	1500	Shale - Sand & Shells
1500	to	1755	Shale & Lime
1755	to	2279	Shale & Sand
2279	to	2319	Anhydrite
2319	to	2330	Shale
2330	to	2876	Lime & Shale
2876	to	2980	Lime
2980	to	3182	Lime & Shale
3182	to	3315	Lime
3315	to	3380	Lime & Shale
3380	to	3575	Lime
3575	to	3835	Lime & Shale
3835	to	4065	Lime
4065			Rotary Total Depth

SET: 278' of 8 5/8" with 140 sacks cement.

SCHLUMBERGER ELECTRIC LOG TOPS:

Topeka	3632	-932
Naebner	3813	-1113
Toronto	3836	-1136
Lansing	3950	-1156
Log Total Depth	4061	

RECEIVED
STATE CORPORATION COMMISSION

DEC 26 1963

CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Transue "B" #1, SW SW NE Section 18-9-36W, Sheridan County, Kansas, as reflected by the files of Empire Drilling Company.

[Signature]
Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 11th day of December, 1963.

[Signature]
Lucille H. Harr, Notary Public

My commission expires October 21, 1966.

