



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
9-20-1974
SEP 20 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mack Oil Company,

Complete Address 812 Union Center, Wichita, Kansas.

Lease Name Littlechild Well No. 2

Location SW-SE-SW Sec. 14 Twp. 11 Rge. (E) (W)24

County Trego Total Depth 4060'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor John O. Farmer, Incorporated,

Address 370 W. Wichita, Russell, Kansas. License No.

Operation Completed: Hour 7:30 PM Day 16 Month 9 Year 1974

The above well was plugged as follows:

203'--8 5/8 " Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 800'.

Circulated hole with heavy mud. Pulled DP to 1025' and displaced 110 Cu. Ft. cement
thru DP from 1025' to 700'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: R. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 9/20/74

INV. NO. 9921-W