


KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
2-5-1969
FEB 5 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name Littlechild Well No. B-1

Location NE-SE-NE Sec. 11 Twp. 11 Rge. (E) (W) 21

County Trego Total Depth 3935'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: R. R. #2, Victoria, Kansas. License No. _____

Operation Completed: Hour 2:30PM Day 1 Month 2 Year 1969

The Above well was plugged as follows:

171'--8 5/8" Surface casing, cement circulated with 125 Sx.
Top of Dakota section @ 735'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 100 Sx. cement thru
DP from 975' to 650'. Pulled DP to 185' and displaced 20 Sx. cement thru DP from 185'
to 125'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. A. F. Nichols*
Well Plugging Supervisor

INVOICED

DATE 2/6/69
INV. NO. 9284-W