

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3-16-1964
MAR 16 1964

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sunray DX Oil Company.

Complete Address: Box # 729, Great Bend, Kansas.

Lease Name A. L. Struss Well No. 2

Location SW-NW-SE Sec. 21 Twp. 11 Rge. (E) (W) 24

County Trego Total Depth 4132

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.,

Address: Box #221, Great Bend, Kansas. License No. 49

Operation Completed: Hour 2:00PM Day 11 Month 3 Year 1964

The Above well, was plugged as follows:

229' -- 8 5/8" Surface pipe, cement circulated with 200 Sx.
4131' -- 5 1/2" production casing cemented on the bottom with 150 Sx. with DV
tool @ 2092' circulated to surface with 90 Bbl. oil & 270 Sx. gel. Well
plugged back to 4097'. Top perforations @ 4026'.
Sanded well back to 4015' and set 5 Sx cement with dump bailer. Pulled 5 1/2"
to 600' and circulated heavy gel mud, (used 22 Sx. gel) then displaced 20 Sx
cement thru 5 1/2". Pulled 5 1/2" to 210' and displaced 30 Sx. cement thru 5 1/2".
pulled 5 1/2" set bridge @ 30' and 15 Sx. cement to bottom of cellar.
(Cementing & Mudding operations performed by Globe Oil Well Cementing Co.)
(Recovered 1524' -- 5 1/2" casing.)

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 3/17/64

INV. NO. 8495-W