

15-195-20148-00-00

Form CP-3
Rev. 6-4-68

KANSAS

20
STATE CORPORATION COMMISSION
RECEIVED
STATE CORPORATION COMMISSION
12-22-1969
DEC 22 1969
CONSERVATION DIVISION
Wichita, Kansas

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mid-America Exploration, Incorporated,

Complete Address Box #302, Chamberlain, South Dakota.

Lease Name Malinowsky Well No. 1

Location CSW-SW Sec. 21 Twp. 11 Rge. (E) (W) 24

County Trego Total Depth 4110'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor B & B Drilling, Incorporated,

Address 207 Petroleum Building, Wichita, Kansas. License No.

Operation Completed: Hour 7:30 AM Day 20 Month 12 Year 1969

The above well was plugged as follows:

208'--8 5/8" Surface casing, cement circulated with 145 Sx.
Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 100 Sx. cement thru
DP from 1150' to 825'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 12/22/69
INV. NO. 1101-W