

15-195-20276-00-00



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
5-15-1974
MAY 15 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name John O. Farmer, Incorporated,
Complete Address Box #352, Russell, Kansas.
Lease Name Struss Well No. B-1
Location SE-SW-SW Sec. 27 Twp. 11 Rge. (E) (W) 24
County Trego Total Depth 4083'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 4:30 PM Day 13 Month 5 Year 1974

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 775'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 110 Cu. Ft. cement
thru DP from 1000' to 675'. Pulled DP to 210' and displaced 30 Cu. Ft. cement thru
DP from 210' to 135'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 5/15/74

INV. NO. 9127-W