

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10-21-1974
OCT 21 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Rains and Williamson Oil Company, Incorporated,

Complete Address 435 Page Court, 320 West Douglas, Wichita, Kansas.

Lease Name Denning Well No. 1

Location SE-SE-SE Sec. 24 Twp. 11 Rge. (E) (W) 24

County Trego Total Depth 4040'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 4:30 AM Day 14 Month 10 Year 1974

The above well was plugged as follows:

205'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 110 Cu. Ft cement
thru DP from 975' to 650'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/23/74
INV. NO. 168-w