

15-195-20014-00-00

Form CP-3
Rev. 6-26-62

KANSAS

10
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
4-21-1967
APR 21 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Glickman Oil Company.

Complete Address: 702 South St. Francis, Wichita, Kansas.

Lease Name Schultz Well No. 1

Location E/2--E/2--NW/4 Sec. 34 Twp. 11 Rge. (E) (W)24

County Trego Total Depth 3876

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 12:00PM Day 18 Month 4 Year 1967

The Above well was plugged as follows:

207'--8 5/8" Surface pipe, cement circulated with 160 Sx.

I was informed by Tool Pusher that severe lost circulation had been encountered while drilling hole. Ran measuring line and found top of fluid @ 465'. Ran DP in hole to 600' and displaced 20 Sx. cement thru DP. Pulled DP and ran measuring line, found top of fluid @ 440'. Pushed plug to 210' and built bridge using hulls and 10' of rock and dumped 20 Sx. cement on top of bridge. Filled hole with heavy mud to 40' and waited 15 minutes to assure 210' plug was holding. Set plug @ 40' and filled hole to bottom of cellar with 10 Sx. cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *H. L. Nichols*
Well Plugging Supervisor

DATE 4/21/67

INV. NO. 5085-W