

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
11-26-1973
NOV 26 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Zenith Drilling Corporation,

Complete Address 200 West Douglas, Wichita, Kansas.

Lease Name Schultz Well No. 1

Location NE-NE-SW Sec. 34 Twp. 11 Rge. (E) (W) 24

County Trego Total Depth 4150'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 1:00 PM Day 16 Month 11 Year 1973

The above well was plugged as follows:

218'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 875'.

Circulate hole with heavy mud. Pull DP to 1100' and displace 110 Cu. Ft. cement thru
DP from 1100' to 775'. Pulled DP to 225' and displaced 30 Cu. Ft. cement thru DP from
225' to 150'. Pulled DP, set bridge @ 140' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

INVOLVED
I hereby certify that the above well was plugged as herein stated.

Date 11/29/73
Inv. No. 8224-W

Signed: *H. L. Dickie*
Well Plugging Supervisor