

*JP*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
5-19-1968  
MAR 19 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Murfin Drilling Company,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name Struss Well No. 1

Location SE-NW-SE Sec. 34 Twp. 11 Rge. (E) (W) 24

County Trego Total Depth 3863'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Above

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 5:00 AM Day 17 Month 3 Year 1968

The Above well was plugged as follows:

270'--8 5/8" Surface pipe, cement circulated with 165 Sx.  
Dakota section from 900' to 1075'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 100 Sx. cement thru  
DP from 1100' to 780'. Pulled DP to 280' and displaced 20 Sx. cement thru DP from 280'  
to 220'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of  
cellar. (Cementing by Allied Cementing Company, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. D. Nichols*  
Well Plugging Supervisor

DATE 3/19/68  
INVOICE NO. 7447-W