

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

15-037-01432-00-00

Lease Operator: MORRIS ENERGY

Address: PO BOX 305 WEIR, KS 66781-0305

Phone: (417) 438-7921 Operator License #: 33495

Type of Well: OIL Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 2-16-09 (Date)

by: JOHN ALMOND (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

CATTLEMAN Depth to Top: 200 Bottom: 220 T.D. 225

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - (PRE-1967)

Lease Name: SAMP

Well Number: sam-47 *nw* *KCC Pkt*

Spot Location (QQQQ): NE - SW - NE - NW

4410 Feet from  North /  South Section Line

3828 Feet from  East /  West Section Line

Sec. 7 Twp. 31 S. R. 22  East  West

County: CRAWFORD

Date Well Completed: N-A, NO RECORD

Plugging Commenced: 2-18-09

Plugging Completed: 2-18-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		SURFACE	20'	6"	IN-PLACE	NONE
		SURFACE	200'	2"	IN-PLACE	NO
CATTLEMAN	OIL	200'	220'			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Washed down 1" steel tubing inside the 2" casing to TD. Pumped 8 sacks of Portland (mixed 6 gallons of water per sack) and circulated cement to surface. Pulled out 1" cementing string and topped off with cement. Installed valve and squeezed 4 sacks of cement to 400 PSI and shut-in. Twelve (12) sacks total. Backside of 2" casing was already cemented and is in good condition.

Name of Plugging Contractor: Morris Energy License #: 33495

Address: PO Box 305 Weir, KS 66781

Name of Party Responsible for Plugging Fees: MORRIS ENERGY (Derek Morris)

State of Kansas County, Crawford, ss.

Derek Morris, owner / operator

RECEIVED


APR 20 2009

KCC WICHITA

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) PO Box 305 WEIR, KS 66781



SUBSCRIBED and SWORN TO before me this 31 day of March 2009

Patricia J. Taveras My Commission Expires: 6-12-10

Notary Public

*PJT*