

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

15-037-01430-00-00

OPERATOR: License #: 33495  
Name: MORRIS ENERGY  
Address 1: PO BOX 305  
Address 2: 3625 NE COAL VALLEY RD.  
City: WEIR State: KS Zip: 66781 + 0305  
Contact Person: DEREK MORRIS  
Phone: ( 417 ) 438-7921  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
CATTLEMAN Depth to Top: 200' Bottom: 220' T.D. 225'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - N-A (Pre-1967)  
Spot Description: \_\_\_\_\_  
NW 7 NW 31 NW 22 Sec. 7 Twp. 31 S. R. 22  East  West  
4,958 Feet from  North /  South Line of Section  
3,833 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: CRAWFORD  
Lease Name: SAMP Well #: SAM-39  
Date Well Completed: N-A  
The plugging proposal was approved on: 2-17-09 (Date)  
by: JOHN ALMOND (KCC District Agent's Name)  
Plugging Commenced: 2-17-09  
Plugging Completed: 2-17-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
CATTLEMAN	OIL	SURFACE	6.5"	20' (?)	NONE

RECEIVED

APR 20 2009

KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran in 1" cementing tubing to 225' TD. Pumped 60 sacks of Portlan mixed 5.5 gallons of water per sack. Circulated cement to surface and pulled 1" string out. Topped-off with cement and installed swedge and ball valve. Squeezed cement to 400 psi and shut-in. On 2-18-09 cut off wellhead 3' below ground level, emptied fluid from pit and backfilled pit. Reclaimed ground to match terrain. \* This well appears to have been an old gas well. There was no 2" pipe in the well.

Plugging Contractor License #: 33495 (Company tools) Name: MORRIS ENERGY

Address 1: PO BOX 305 Address 2: 3625 NE COAL VALLEY RD.

City: WEIR State: KANSAS Zip: 66781 + 0305

Phone: ( 417 ) 438-7921

Name of Party Responsible for Plugging Fees: MORRIS ENERGY

State of KANSAS County, CHEROKEE, ss.

DEREK MORRIS  
(Print Name)  Employee of Operator or  Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Derek Morris

Patricia J. Tavernaro  
NOTARY PUBLIC PATRICIA J. TAVERNARO  
6-12-10  
2078 Wichita, Kansas 67202

PKT