


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Trego County, Sec. 2 Twp. 11S Rge. 25W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE SW NE

Lease Owner The National Oil Company
Lease Name Tidball Well No. 1
Office Address Suite 550, O.W. Garvey Bldg., Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole
Date Well completed February 23, 1977
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced February 23, 1977
Plugging completed February 23, 1977
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 4050

Show depth and thickness of ~~ad~~ water, oil and gas formations.

OIL, GAS OR WATER RECORDS RECEIVED
STATE CORPORATION COMMISSION
3-7-1977
MAR 07 1977
CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
CONSERVATION DIVISION Wichita, Kansas				8-5/8"	241'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 4,050 ft. (rotary total depth) to 1,000 ft. Set plug at 1,000 ft. and cemented with 75 sacks cement. Filled hole with heavy rotary mud from 1,000 ft. to 225 ft. Set plug at 225 ft. and cemented with 20 sacks cement. Filled hole with heavy rotary mud from 225 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 2 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4-1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Building, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Dean Britting, Agent (employee of owner) or (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 No. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of March, 19 77

Elsie Willison
Elsie Willison - Notary Public.

My commission expires June 30, 1978



15-195-20392-00-00

KANSAS GEOLOGICAL SOCIETY API NO. - 15-195-20,392
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY The National Oil Company

SEC. 2 T. 11S R. 25W
LOC. NE SW NE


FARM Tidball NO. 1

TOTAL DEPTH 4,050'
COMM. February 15, 1977

COMP. February 23, 1977

COUNTY Trego
KANSAS

SHOT OR TREATED
CONTRACTOR H-30, Inc.
ISSUED February 4, 1977



CASING
20 10
15 8
12 6
13 5

-5/8" 241' cemented w/200 sxs cement ELEVATION 2416' KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	100'
Shale and Sand	1,465'
Shale and Red Bed	2,063'
Anhydrite	2,094'
Shale and Lime	3,521'
Lime	4,050'
Rotary Total Depth	4,050'

RECEIVED
STATE CORPORATION COMMISSION
3-7-1977
MAR 07 1977
CONSERVATION DIVISION
Wichita, Kansas


I hereby certify the above and foregoing to be
a true and correct log of the above described
well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public
in and for said county and state this 4th. day
of March, 1977.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
June 30, 1978