

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

15-0 49-20467-00-00

Lease Operator: Lone Wolf Oil dba
Address: Box 241 Moline, Ks 67353
Phone: (620) 647-3626 Operator License #: 31119
Type of Well: Oil Docket #:
The plugging proposal was approved on: 8-26-08
by: Duane Sims (KCC District Agent's Name)
Is ACO-1 filed? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Mississippi Depth to Top: 2298 Bottom: 2310 T.D. 2310
Kansas City Depth to Top: 1676 Bottom: 1682 T.D. 1950

API Number: 15 - unknown
Lease Name: Wiseman
Well Number: 4
Spot Location (QQQQ): NW
1240 Feet from North South Section Line 4116
75 Feet from East West Section Line 5213
Sec. 13 Twp. 31 S. R. 9 East West
County: Elk
Date Well Completed: 1-28-78
Plugging Commenced: 8-26-08
Plugging Completed: 8-26-08

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Surface, Mississippi, and Kansas City.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Bridge plug at 1950 ft. Ran tubing to 1950 ft. Mix 15 sx. 60/40 pozmix cement with 4% gel. Pumped to bottom. Pulled tubing 750 ft. Pumped gel spacer. Pulled tubing. Perf. well at 753 ft. Hooked up to 4 1/2 casing and pumped 15 sx. cement. Shoot pipe at 504 ft. Mix and pump 150 sx. 60/40 pozmix cement with 4% gel and circulate to top. Pulled casing and topped off with cement.

Name of Plugging Contractor: C & G Drilling Inc. License #: 32701
Address: 303 S. High Eureka, Ks. 67045

RECEIVED APR 29 2009

Name of Party Responsible for Plugging Fees: Lone Wolf Oil dba
State of Ks. County, Elk

KCC-WICHITA

Rob Wolfe (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Robert Wolfe

(Address) Box 241 Moline, Ks. 67353

LISA J. TOWNSLEY Notary Public - State of Kansas My Appt. Expires 6-13-12

SUBSCRIBED and SWORN TO before me this 14th day of October 2008. Lisa J. Townsley Notary Public My Commission Expires: 6-13-2012

Handwritten initials/signature