

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: McCoy Petroleum Corporation

Address: 8080 E. Central, Suite #300, Wichita, KS 67206-2366

Phone: 316-636-2737 x 104 Operator License # 5003

Type of Well: Oil Coas KCCPT Per Open - Dave
(If SWD or ENHR)

The plugging proposal was approved on: 4/1/09 (Date)

by: Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Miss Depth to Top: 4673' Bottom: 4685' + T.D. 4690'
Depth to Top: Bottom: T.D.
Depth to Top: Bottom: T.D.

API Number 15-047-21479-0000

Lease Name: WETZEL "R" GU #2-27

Well Number: #2-27

Spot Location (QQQQ): 50'N of S2 S2 SE

710 380 Feet from North / South Section Line

1320 Feet from East / West Section Line

Sec 27 Twp 25 S. Rng. 20 East West

County: Edwards

Date Well Completed: 12/4/06

Plugging Commenced: 4/8/09

Plugging Completed: 4/9/09

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows show casing sizes of 8 5/8" and 4 1/2" with corresponding depths.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

4/9/09: MIRU. Dumped sand at 4600'. Bailed 4 sacks cement. Ripped casing at 2440', worked pipe. Ripped casing at 2310' and pipe came free. Pulled casing up to 1390' and pumped 15 gel, 50 sacks cement. Pulled casing up to 360' and pumped 50 sacks cement. Pulled to 40' and pumped 20 sacks cement to surface. Emptied pit, cut casing head off, and cleaned up location.


Name of Plugging Contractor: Quality Well Service License #: 31925

Address: 190th US 56 Highway, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation

State of Kansas County, Sedgwick, ss.

Scott Hampel - Employee of Operator (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Scott Hampel

(Address) 8080 E. Central, Suite #300, Wichita, KS 67206-2366

SUBSCRIBED and SWORN TO before me this 21st day of April 20 09

Brent B Reinhardt My Commission Expires: 12/7/2011
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

APR 22 2009

KCC WICHITA