

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: McCoy Petroleum Corporation

Address: 8080 E. Central, Suite #300, Wichita, KS 67206-2366

Phone: 316-636-2737 x 104 Operator License #: 5003

Type of Well: Gas Oil KCCPT per open-Dave Docket #: (If SWD or ENHR)

The plugging proposal was approved on: 4/1/09 (Date)

by: Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? [X] Yes [ ] No If not, is well log attached? [ ] Yes [X] No

Producing Formation(s): List All (If needed attach another sheet)

Miss Depth to Top: 4678' Bottom: 4693' T.D. 4696'
Ft Scott & Pawnee Depth to Top: 4546' Bottom: 4586' T.D. 4696'
LKC "A" & "B" Depth to Top: 4075' Bottom: 4120' T.D. 4696'

API Number 15-047-21476-0000

Lease Name: FROETSCHNER-BIRZER #2-33 Unit

Well Number: #2-33

Spot Location (QQQQ): 150' W of NE NE SE W2 KCCPT per CP2/3

2310 Feet from [ ] North / [X] South Section Line

480 Feet from [X] East / [ ] West Section Line

Sec 33 Twp 25 S. Rng. 20 [ ] East [X] West

County: Edwards

Date Well Completed: 5/9/03

Plugging Commenced: 4/6/09

Plugging Completed: 4/7/09

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes handwritten 'RECEIVED APR 22 2009 KCC WICHITA'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

4/7/09: MIRU. Pumped 60 sacks cement, 200# hulls, displaced down 4 1/2" casing. Shut-in and pressured up to 300# psi. Checked hole at cement was at 3620'. Ripped casing at 2810', worked pipe. Ripped casing at 2640', worked pipe. Ripped casing at 2520' and pipe came free. Pulled casing up to 1390' and pumped 15 gel, 50 sacks cement, 50# hulls. Pulled casing up to 360' and pumped 50 sacks cement, 50# hulls. Pulled to 40' and pumped 25 sacks cement to surface. Emptied pit and cleaned up location.


Name of Plugging Contractor: Quality Well Service License #: 31925

Address: 190th US 56 Highway, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation

State of Kansas County, Sedgwick, ss.

Scott Hampel - Employee of Operator (Employee of Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Scott Hampel

(Address) 8080 E. Central, Suite #300, Wichita, KS 67206-2366

SUBSCRIBED and SWORN TO before me this 21st day of April 20 09

Brent B Reinhardt My Commission Expires: 12/7/2011 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202