

15-163-19060-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 16 Twp. 10S Rge. (E) 16 (W)
Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner White & Ellis Drilling, Inc. & Petroleum, Inc.
Lease Name Conger Well No. B-1
Office Address Box 448, El Dorado, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 21, 19 61
Application for plugging filed August 21, 19 61
Application for plugging approved August 21, 19 61
Plugging commenced August 21, 19 61
Plugging completed August 21, 19 61
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3650 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	242'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy rotary mud to 240 feet. Plug at 240 feet, dumped hulls & 15 sacks cement thru drill pipe. Mud to 40 feet, plug at 40 feet, dumped hulls & 10 sacks cement. Dumped hulls & 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
8-30-61
AUG 30 1961
CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor White & Ellis Drilling, Inc. - License #209
Address Box 448 - El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
Ernest Sifford, employee of Contractor (employee of owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford
Box 448, El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of August, 19 61

My commission expires September 26, 1961 L. B. Auer Notary Public.

15-163-19060-0000

Casing Record

Location: SE SE NE
Section: 16-10S-16W
Rooks County, Kansas
Farm: Conger B-1
Well Owner: Petroleum, Inc.
Contractor: White & Ellis Drig., Inc.
Started: 8/9/61
Completed: 8/21/61
Elevation: 2080' D.F.

8 5/8

242' Cemented
w/150 sacks

T. D. 3650'

Kelly Bushing Measurement 5' above ground level.

FORMATION	DEPTH
Lime	0-90
Shale & post rock	242
Shale	405
Shale & Lime stks.	560
Shale & Sand	615
Shale	635
Sand & Shale	940
Shale	1015
Red bed	1255
Anhydrite	1288
Shale & Shells	1780
Anhydrite & Shale	1830
Anhydrite	1890
Shale, Lime & Shales	2000
Shale & Lime	2075
Lime & Shale	2630
Shale & Lime	2735
Shale	2810
Lime & Shale	2956
Lime	3186
Shale	3189
Lime & Shale	3208
Lime	3217
Lime & Shale	3230
Lime	3512
Lime & Shale	3555
Lime	3558
Conglomerate	3614
Lime	3650

TOPS

Topeka	2957
Heebner	3186
Lansing	3230
Kansas City	3287
Conglomerate	3558
Arbuckle	3614

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1961
CONSERVATION DIVISION
Wichita, Kansas