


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 34 Twp. 10 Rge. 16 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NW SW
Lease Owner V. D. Sidey Oil Co.
Lease Name Nelson Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 4-23-50 19
Application for plugging filed 4-23-50 19
Application for plugging approved 4-23-50 19
Plugging commenced 4-23-50 19
Plugging completed 4-23-50 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3626 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	92	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud to 92'. Set plug & filled hole to bottom of cellar with 30 sacks cement.

5-2-50
MAY 2 - 1950

ST. ...
COMM. DIV.
KANSAS

(If additional description is necessary, use BACK of this sheet)


Correspondence regarding this well should be addressed to V. D. Sidey
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Murfin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.R. Murfin

910 Union Natl. Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of April, 19 50
My commission expires 3-5-52
Genevieve Hays Notary Public.



15-163-00280-000.0

KANSAS WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY V. D. Sidey Oil Co.

SEC. 34 T. 10 R. 16W

LOC. SE NW SW

FARM Nelson

NO. 1

COUNTY Rooks

TOTAL DEPTH 3626

COMM. 4-10-50

COMP. 4-23-50

SHOT OR TREATED

CONTRACTOR Murfin Drilling Co.

ISSUED

CASING

20 10
15% 8 1/4 92
12% 6%
13% 5 1/4

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 30 shells & shale
- 40 gray shale
- 70 black shale & shells
- 90 black shale
- 92 lime shell
- 155 black shale & shells
- 390 gray shale & shells
- 405 gray sand
- 450 shale & shells
- 490 brown sand
- 610 shale & shells
- 625 gray sandy shale & shells
- 655 sand, blue shale
- 715 blue shale & sand
- 719 gray sand rock
- 780 blue shale & shells
- 825 sand & gray shale
- 895 blue shale & shells
- 1175 red bed & shale
- 1203 anhydrite
- 1220 shale
- 1445 shale & shells
- 1535 shale & hard lime shells
- 1795 shale & shells
- 1860 gray lime
- 1930 brk. white lime
- 1995 white lime
- 2025 white lime & shale
- 2205 lime & shale
- 2525 shale
- 2620 gray lime, red & gray shale
- 2780 shale & shells
- 2965 shale & lime
- 3175 lime
- 3502 brkn. lime
- 3370 lime
- 3420 lime & shale
- 3490 lime
- 3565 lime & shale
- 3578 congl.
- 3626 Arb. lime
- T.D.

MAY 2 - 1950

STATE CORPORATION COMMISSION KANSAS

STATE OF KANSAS)

SEDGWICK COUNTY)

SS:

PLUGGING
 FILE SEC. 34 T. 10 R. 16W
 BOOK PAGE 2 LINE 48

I, W. R. Murfin, of the Murfin Drilling Company, a partnership, contractor engaged for the drilling of the Nelson No. 1 well, located in the SE NW SW of Section 34, Township 10, Range 16 West, Rooks County, Kansas, upon oath state that the above and foregoing is a true and correct copy of the log of said well.

W. R. Murfin
W. R. Murfin

Subscribed and sworn to before me this 27th day of April, 1950
My Commission Expires: 3-5-52

L. J. ...

