

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Rooks County, Sec. 34 Twp. 10 Rge. 16 E/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
SE SE NE

Lease Owner R. P. Nixon Operations  
Lease Name Nelson #1 Well No. \_\_\_\_\_  
Office Address Hays, Kansas 67601  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced ~~6/3/79~~ 6/5/79 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 6/12/79 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation  
depleted  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_



Locate well correctly on above  
Section Plot

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Schmidt  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 9600  
Show depth and thickness of all water, oil and gas formations. 3380

RT  
KCC

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	228	none
				4 1/2"	3380	2529'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed plug to 3000' and ran 5 sacks cement. Loaded hole, shot pipe at 2413', pulled 81 joints. Pumped 1 sack hulls, 16 sacks gel, 140 sacks 50-50 pos, 6% gel.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 18 1979  
6-18-79

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

CONSERVATION DIVISION  
Wichita, Kansas  
SS.

STATE OF KANSAS COUNTY OF RICE  
R. DARRELL KELSO (employee of owner) or (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS

SUBSCRIBED AND SWORN TO before me this 15th day of June, 19 79

Margaret Melcher  
Notary Public.

My commission expires \_\_\_\_\_



15-163-30188-0001

ROTARY DRILLING LOG

Operator: Omega Drilling, Inc.  
#1 Nelson  
SE SE NE Sec. 34-10S-16W  
Rooks County, Kansas

Contractor: Omega Drilling, Inc.  
Commenced: December 17, 1965  
Completed: December 31, 1965

Remarks: Set 8 5/8" surface casing @ 228' w/205 sx HA5

FORMATIONS

0 - 228	Top soil, Shale
228 - 921	Shale and Sand Streaks
921 - 1389	Shale and Anhydrite
1389 - 1905	Shale and Shells
1905 - 2131	Shale and Lime
2131 - 2285	Lime
2285 - 2450	Lime
2450 - 2730	Shale and Lime
2730 - 2972	Shale and Lime
2972 - 3055	Lime
3055 - 3150	Shale and Lime
3150 - 3185	Lime
3185 - 3270	Lime
3270 - 3330	Lime with Shale
3330 - 3345	Lime
3345 - 3400	Lime
3400 - 3478	Lime
3478 - 3539	Lime
3539 - 3577	Lime
3577 - 3600	Lime
3600 -	RTD

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 22 1979  
CONSERVATION DIVISION  
Wichita, Kansas

Aug 13, 1971 - Rework data

Moved in Jayhawk Drlg. Co. cable tools and washed hole down. Set 4 1/2" casing at 3380' with 175 sks. Perforated and acidized Toronto Lime from 3212.5' to 3215.5'. Swabbed 3 bbls. fluid per hour 75% oil. Put on pump Sept 5, 1971.

We certify that the above log is true and correct to the best of our knowledge and belief.

OMEGA DRILLING, INC.

R. P. Nixon Operations

By: *R. P. Nixon*

F. S. Woodside, Jr.  
Executive Vice-President

Subscribed and sworn to before me, a Notary Public, in and for the State of Kansas, County of Sedgwick, this 17<sup>th</sup> day of January, 1966.

My commission expires January 8, 1968 *Louis J. ...*