


15-163-02429-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County Sec. 35 Twp 10 Rge. (E) 16 (W)

Location as "NE/CNW4SW4" or footage from lines: 990' N 990' S of Center
Lease Owner: Citiles Service Oil Co.
Lease Name: Krueger Well No. 5
Office Address: Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole
Date well completed: 11-18 19 49
Application for plugging filed: 11-18 19 49
Application for plugging approved: 11-18 19 49
Plugging commenced: 11-18 19 49
Plugging completed: 11-18 19 49
Reason for abandonment of well or producing formation:



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production: 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well: Mr. Eldon Petty
Producing formation: Lansing-K.C. Depth to top: 3280 Bottom: Total Depth of Well: 3692 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lansing-K.C.	Dry			8-5/8"	300	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Filled with mud from total depth to 295 feet, set plug dumped 15 sacks cement. Mud to 30 feet, set plug dumped 10 sacks cement, mud and dirt to surface.

RECORDED
INDEXED
NOV 7 1950

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: Mr. S. C. Cooper
Address: Box 751, Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON ss
Mr. James Porter (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) James Porter
Box 553, Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of December 1949
My commission expires 3-17-1951

PLUGGING
FILE SEC 35 T 10 R (cc)
BOOK PAGE 125 LINE 16

WELL RECORD

Company Citico Service Oil Co. Well No 5 Farm Krueger
 Location 990' South and 990' East of Center Sec 35 T 10 R 16W
 Elevation 2094 (2092 Gr.) County Rooks State Kansas
 Drlg. Comm November 7, 1949 Contractor Helm Drilling Company
 Drlg. Comp November 18, 1949 Acid None
 T. D. 3692' Initial Prod. None - P. & A. 11-18-49

CASING RECORD:

8-5/8" @ 300' cen. 175 ex cement

FORMATION RECORD:

SHALE	0-40
shale & shells	530
sand	560
sand, shale & shells	985
red bed	1250
anhydrite	1290
shale & shells	1890
shale & lime	1985
lime & shale	2230
lime	2320
lime & shale	2545
shale & shells	2565
shale & lime	2710
lime & shale	2860
shale & lime	2980
lime	3640
conglomerate	3660
lime	3692 TD

Top Topeka	2992'
Top Heebnor	3231'
Top Dodge	3255'
Top Lansing	3280'
Top Cherty Conglomerate	3611'
Top Simpson Dolomite	3653'
Top Simpson Sand	3676'
Top Arbuckle	3679'
Penetration	13'
Total Depth	3692'

BYFO: 500' 0°
 1000' 0°
 1500' 1°
 2000' 0°
 2500' 0°
 3000' 0°

7-7/8" rotary hole.

Ron Schlumberger elec. log.

PLUGGING
 FILE SEC 35 T 10 R 16
 BOOK PAGE 105 LINE 16

JAN 7 X 1950
 OIL COMMISSION
 KANSAS