


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 34 Twp. 10S Rge. 16 (E) 16 (W)
Location as "NE/CNW/SW" or footage from lines SE SW NE
Lease Owner Magnolia Petroleum Company
Lease Name Hans NELSON Well No. 1
Office Address Box 900 Dallas, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 6-21-54 19
Application for plugging filed 6-22-54 (Verbal 6-21-54) 19
Application for plugging approved 6-23-54 (Verbal 6-21-54) 19
Plugging commenced 6-21-54 19
Plugging completed 6-21-54 19
Reason for abandonment of well or producing formation Well drilled dry

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 3515 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None				9 5/8"	150'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/heavy rotary mud to 150'; set #1 plug @ 150',
1/2 sx hulls 15 sx cmnt on top of plug, filled hole to 40';
1/2 sx hulls 10 sx cmnt dumped on top of plug #2, filled hole
to bottom of cellar.
All mudding & plugging done as per Mr. Eldon Petty, state plugger.

9-13-54
DIVISION
KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barnett Drilling Company
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
C. A. Hill (employee of owner) ~~not a contractor~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 770 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of September, 19 54
Harriett S. Kaiser
Notary Public.

My commission expires 1-14-57

PLUGGING
FILE SEC-34-10-2/6W
BOOK PAGE 42 LINE 36

15-163-02525-0000

MAGNOLIA PETROLEUM COMPANY

WELL RECORD

Hans NELSON #1 D & A
SE SW NE Sec. 34-10S-16W
Rooks County, Kansas

Krueger Field

Spudded: 6-6-54
Completed: 6-21-54 D & A
Plugged and abd. 6-21-54

Drilled By: Barnett Drilling Co., Wichita, Kansas

9 5/8" set @ 150' w/125 sx cmnt circ. 6-7-54


Shale & Shells	0	630
Sand	630	850
Sandy Shale	850	1000
Red Bed	1000	1100
Anhydrite	1100	1135
Shale & Shells	1135	1760
Lime & Shale	1760	1960
Lime	1960	2215
Shale & Lime	2215	2330
Lime & Shale	2330	2770
Shale & lime	2770	2885
Lime	2885	3372
Lime & Shale	3372	3465
Lime & Chert	3465	3510
Lime	3510	3515
Total Depth	3515	

Total Depth	3515
Plug Back Depth	Dry & Abandoned
Oil String Set @	None

RECEIVED
STATE CORPORATION COMMISSION

SEP 15 1954

CONSERVATION DIVISION
Wichita, Kansas



PLUGGING
 FILE SEC
 BOOK PAGE