

15-073-24092 -00-00

5-24-12E

# RIG 6 DRILLING COMPANY, INC.

PO BOX 227  
IOLA, KANSAS 66749

R.K. (Bud) Sifers  
(620) 365-6294

John J. Barker  
(620) 365-7806

COMPANY Lockard Petroleum  
ADDRESS: 806 Melanie Ct.  
Liberty, MO 64068

LEASE: Beuchat  
COUNTY: Greenwood  
LOCATION 2970'FSL/3300'FEL  
5/24/2012

COMMENCED: 8/11/2008  
COMPLETED: 8/14/2008  
WELL #: 1/18  
API#: 15-073-24,092-24092-0000  
STATUS: Dry  
TOTAL DEPTH: 1865'-6 3/4"  
CASING: 40'-8 5/8" cmt w/ 20 sx

## DRILLER'S LOG

8	soil & clay	1467	Sh
14	Sh (Shale)	1469	LS
19	Limestone (Ls)	1523	Sh
46	Sg	1526	LS
59	Ls	1605	Sh
86	Sh	1607	Sa Sh lt odor
153	Ls w/ sh brks	1621	Sh
279	Sh w/ ls strks	1622	Sh (blk)
365	LS w/ shs trks	1760	Sh
604	Sh	1762	Co
631	Ls w/ sa ls	1778	Sh
682	Sh	1806	LS
752	Ls	1816	ls Sa (good odor)
773	SA Sh	1865	LS T.D.
808	Ls		
917	Sh		
921	LS		
941	Sh		
960	LS		
980	Sh		
1123	LS w/ sh brks		
1262	Sh		
1301	LS		
1353	Sh		
1427	LS w/ sh brks		

Plugging Report:  
50' plug @ T.D.  
50' plug @ 1100' (Base KC)  
275' to surface  
Consolidated Cement  
plug down at 5:00 pm  
plug ok'd by Russell @ KCC Chanute

RECEIVED  
KCC DISTRICT #:

OCT 17 2008

CHANUTE, KS

RECEIVED

NOV 17 2008

KCC WICHITA



**CONSOLIDATED**  
Oil Well Services, L.L.C.

**ENTERED**

TICKET NUMBER 19195  
LOCATION EUREKA  
FOREMAN Rick Leaford

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-17-08	4922	Beuchat #18				GW
CUSTOMER			TRUCK #			
MAILING ADDRESS			DRIVER			
CITY			TRUCK #			
STATE			DRIVER			
ZIP CODE						

CUSTOMER: LOCKHART PETROLEUM, INC.  
 MAILING ADDRESS: 806 MEADEN CL  
 CITY: LIBERTY STATE: Mo. ZIP CODE: 64968  
 JOB TYPE: P.T.A HOLE SIZE: 6 3/4" HOLE DEPTH: 1965' CASING SIZE & WEIGHT: \_\_\_\_\_  
 CASING DEPTH: \_\_\_\_\_ DRILL PIPE: \_\_\_\_\_ TUBING: \_\_\_\_\_ OTHER: \_\_\_\_\_  
 SLURRY WEIGHT: \_\_\_\_\_ SLURRY VOL: \_\_\_\_\_ WATER gal/sk: \_\_\_\_\_ CEMENT LEFT in CASING: \_\_\_\_\_  
 DISPLACEMENT: \_\_\_\_\_ DISPLACEMENT PSI: \_\_\_\_\_ MIX PSI: \_\_\_\_\_ RATE: \_\_\_\_\_

REMARKS: Safety meeting - Rig up to 3 1/2" drill pipe. Plugging order as follows:

- 15 SKS @ 1860'
- 15 SKS @ 1118'
- 70 SKS @ 275' to surface

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5450	1	PUMP CHARGE	925.00	925.00
5406	20	MILEAGE	3.65	73.00
1181	100 SKS	100/40 Premix cement	11.35	1135.00
1118A	345 #	470 gal	.17	58.65
5407	4.3	two-mileage bulk tank RECEIVED	m/c	315.00
55026	4 hrs	80 Bbl vac TRK NOV 17 2008	100.00	400.00
1123	3000 gals	city water	14.00 per 1000	42.00
		KCC WICHITA		
		RECEIVED KCC DISTRICT #3		
		OCT 17 2008		
		CHANUTE, KS		
		Subtotal		2948.65
		SALES TAX		77.80