

WELL RECORD

15 163-04039-0001
Krueger Unit
C#301W

Company Cities Service Oil Co. Well No. 1 Farm Gish "A" S. W. D.
 Location 990' North and 330' East of SW Cor. Sec. 36 T. 10 R. 16W
 Elevation 2062 County Hooks State Kansas
 Drlg. Comm. July 20, 1952 Contractor Folger Drilling Company
 Drlg. Comp. August 22, 1952 Acid None
 T. D. 3877' Initial Prod. Input Test: Ind. capacity 1140 bbls. per hr. (8-22-52)

DEEPENING FOR SALT WATER DISPOSALCASING RECORD:

8-5/8" @ 295' cem. 150 sz cement
 5-1/2" @ 3555' cem. 175 sz cement

187' of 4-1/2" liner at 3682' with
 50 sz cement.

FORMATION RECORD:

Old T. D. 3555

Cement squeezed Lansing-Kansas City
 perforations.

lime	3555-3586
conglomerate	3642
conglomerate & shale	3666
lime	3690
	3690 RTD = 3682 SLH
lime	3877' T. D.

Top Lansing	3241'
Corr. Conglomerate	3574'
Corr. Eros. Simpson	3632'
Corr. Simpson Dolomite	3636'
Corr. Simpson Sand	3655'
Corr. Arbuckle	3657'
Penetration	220'
Total Depth	3877'

10-23-53 TO 12-2-53 Repr. cog
 leaked CO to O.T.D.
 HOLES @ 831-34 and 882
 (2 SQUEEZE JOBS)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 03 1993

CONSERVATION DIVISION
 Wichita, Kansas