

WELL RECORD

Company Cities Service Oil Company Well No. 3 Farm Lindquist "A"
 Location 2395 FSL 2310 SWL Sec. 15 T. 10S R. 16W
 Elevation 1945 K.B., 1942 D.F. County _____ State Kansas
 Initial Prod. _____ Contractor Peel Bros.
 Acid _____ Drlg. Comm. 2-8-66
 T.D. 3510' Drlg. Comp. 3-17-66

Casing Record:

3 5/8" at 290 W/200 sacks
 4 1/2" at 3509 - D.V. Tool at 1129
 Lower Stage 250 Sx. - Upper Stage 400 Sx.

Formation Record

Formation	Depth
Shale	0-
Sand and Red bed	440
Sand	600
Red Bed	610
Anhydrite	1110
Shale and Shells	1155
Lime and Shale	1653
Lime	3005
Conglomerate	3440
	3510

Electric Log Tons:

Topoka	2816'	(-871)
Hobbs	3048'	(-1103)
Toronto	3069'	(-1124)
Lansing	3092'	(-1147)
Base Kansas City	3365'	(-1420)
Conglomerate	3419'	(-1474)
Arb.	3488'	(-1543)
LTD	3507'	

Slope Test: Eastman

500'	1/4°
1000'	1/4°
1528'	1/4°
2094'	1/2°
2515'	1/4°