

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-20088-00-00
Spot: SENESW Sec/Twnshp/Rge: 32-16S-19W
1649 feet from S Section Line, 3127 feet from E Section Line
Lease Name: OHNMACHT Well #: 7
County: RUSH Total Vertical Depth: 3805 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	147		
DVT		1266		WITH 375 SX CMT
PROD	4.5	3798	0	

Well Type: OIL UIC Docket No: Berexco Inc Date/Time to Plug: 04/14/2009 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY KCCPKT
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO Phone: (316) 265-3311

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

123.66

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/14/2009 4:50 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SHOT OFF 2 7/8" TBG @ 3775'. COULDN'T PULL, TRY CIRCULATING. SQUEEZED @ 3150' WITH 290 SX CMT. SQUEEZED @ 912-943' WITH 75 SX CMT. BACKED OFF TBG @ 1226'. PULLED OUT OF HOLE & INSPECTED. RAN TBG BACK TO 1225'. PUMPED 90 SX CMT CIRCULATING CMT TO SURFACE UP 4 1/2". PULLED TBG. PUMPED 45 SX CMT DOWN 4 1/2". MAXIMUM PRESSURE 750 PSI. SHUT IN PRESSURE 500 PSI. PUMPED 215 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. MAXIMUM PRESSURE 300 SPI. SHUT IN PRESSURE 100 PSI.

Perfs:

Top	Bot	Thru	Comments
3798	3805	OH	

INVOICED
DATE: 5-6-09
INV. NO. 2009061491

RECEIVED
APR 22 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
APR 17 2009
KCC DODGE CITY

Signed Richard W. Lacey
(TECHNICIAN)