

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-19051-00-01
Spot: SWSEW Sec/Twnshp/Rge: 15-29S-7W
2310 feet from N Section Line, 1650 feet from W Section Line
Lease Name: BIRKENBAUGH COWWO Well #: 1
County: KINGMAN Total Vertical Depth: 4510 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP	5.5	3890		
PROD	5.5	4510		
SURF	8.625	250		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/18/2009 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK 50' ABOVE THE PERFS AND CAP WITH 5 SKS OF CMT. RECOVER CASING. 325 SKS 1100', 35 SKS 700'. CIRC FROM 300'-0'.
146.58

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 03/18/2009 11:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3750', AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 2280' AND PULLED TO 1100', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 700', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 300', WHERE CMT WAS CIRCD TO SURFACE. THE REMAINING CASING WAS PULLED AND THE CASING WAS TOPPED OFF.

Perfs:

INVOICED
DATE 5-6-09
INV. NO. 2009061514


RECEIVED
KANSAS CORPORATION COMMISSION
APR 15 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

PKA