

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21211-00-00
Spot: SESESE Sec/Twnshp/Rge: 9-25S-9W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: BECK Well #: 1-9
County: RENO Total Vertical Depth: 4030 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4026	2456	175 SX
SURF	8.625	212		175 SX

130.98

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/25/2009 1:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: RAMA OPERATING CO. Phone: (620) 234-5191

Proposed Plugging Method: ACCORDING TO THE RULES AND REGULATIONS OF THE K.C.C.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 03/25/2009 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED TO 3800' TOPPED WITH 5 SXS OF CEMENT. RIPPED CASING OFF AT 2456', PULLED CASING TO 1469' PUMPED 15 SACKS OF GEL DOWN TUBING, DISPLACED, GEL DID NOT CIRCULATE TO SURFACE, THEN SPOTTED 35 SX OF CEMENT, PULLED CASING TO 787' SPOTTED 35 SXS OF CEMENT PULLED CASING TO 275' SPOTTED 35 SX OF CEMENT PULLED CASING TO 64' CIRCULATED 35 SX OF CEMENT TO SURFACE. CHECKED TOP PLUG ON 3/26/2009 FELL BACK 140'. ON 4/7/2009 FILLED SURFACE WITH 30 SX OF CEMENT, COPELAND, GREAT BEND.

Perfs:

Top	Bot	Thru	Comments
3860	3874		

INVOICED
DATE 5-6-09
INV. NO. 2009061515

KANSAS CORPORATION COMMISSION

APR 16 2009
RECEIVED

Remarks: COPELAND/GREAT BEND-TICKET #35270 60/40 4% GEL - POS MIX

Plugged through: CSG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

PKS

JK