

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21202-00-01
Spot: W2NWSW Sec/Twnshp/Rge: 20-12S-20W
1980 feet from S Section Line, 4950 feet from E Section Line
Lease Name: ERBERT Well #: 4
County: ELLIS Total Vertical Depth: 3950 feet

Operator License No.: 32705
Op Name: RANEY OIL COMPANY, LLC
Address: 3425 TAM O SHANTER
LAWRENCE, KS 66047

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	198	0	w/250 sxs cmt
PROD	4.5	3950	0	w/350 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/16/2009 11:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: IRVIN HASELHORST Company: RANEY OIL COMPANY, LLC Phone: (785) 623-1154

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 10 sxs gel.
Squeezed at 1560' w/350 sxs in 1989.
Fluid level at 2700'.

128.38

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/17/2009 8:15 AM KCC Agent: PAT STAAB

Actual Plugging Report:

04/16/2009 - Allied rigged to 4 1/2" casing - pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in - followed with 10 sxs gel.
Pumped 235 sxs 60/40 pozmix - 4% gel with 300# hulls mixed in.
Well went on vacuum. Left set - fluids down 400'.
04/17/2009 - Topped off with 20 sxs cement. Hole standing full.
Rigged to 8 5/8" - pumped 45 sxs cement.
Max. P.S.I. 200#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3836	3847		

INVOICED
DATE: 5-6-09
INV. NO. 2009061514

RECEIVED
APR 22 2009
KCC WICHITA

Remarks: WELL ORIGINALLY KNOWN AS ERBERT #1. ALLIED CEMENTING COMPANY-TICKET #34976A.

Plugged through: CSG

District: 04

Signed [Signature]
(TECHNICIAN)

CM [Signature]

A. SCOTT RITCHIE #1 ERBERT 20-12-20W
 SUITE 950, 125 N. MARKET W/2 NW SW
 WICHITA, KS.
 CONTR MURE IN DR LG. CO. CTY ELLIS
 GEOL _____ FIELD KELL EXT (1/8 E)
 E 2234 KB CM 8/2/76 CARD ISSUED 9/16/76 IP D&A/ARB
 8/13/76

+	+
+	+

API 15-051-21,202

SMP	TOPS	DEPTH	DATUM	
ANH	1599	+ 635		8-5/8" 198/160sx
B ANH	1645	+ 589		DST (1) 3288-3303/30-45-45-60, REC 20'
TOP	3269	-1035		TM, SIP 1140-1128#, FP 50-100#, 125-188#
HEEB	3501	-1267		DST (2) 3474-3495/40-45-45-60, REC 120'
TOR	3519	-1285		WM, SIP 1237-1225#, FP 38-50#, 50- 75#
LANS	3537	-1303		DST (3) 3529-3551/30-45-45-60, 30'SOCM, 60' O&GCM, SIP 263-380#, FP 50-63#, 63-75#
BKC	3781	-1547		DST (4) 3562-3582/30-45-45-60, 920'SOC SW, SIP 754-754#, FP 63-300#, 325- 488#
ARB	3916	-1682		DST (5) 3652-3705/30-45-45-30, 70'M (NS) SIP 1056-1007#, FP 50-75#, 75-88#
RTD	3944	-1710		DST (6) 3698-3770/30-30-30-30, 80'M (NS) SIP 1068-1043#, FP 75-88#, 88-88#

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

A. SCOTT RITCHIE #1 ERBERT 20-12-20W
 W/2 NW SW
 DST (7) 3918-3923/30-30-30-30, REC 15'SOCM, (SFO), SIP 935-
 657#, FP 25-38#, 38-38#
 DST (8) 3923-3933/30-30-30-30, REC 5'M (NS), SIP 63-50#, FP
 25-25#, 25-25#