

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-20063-00-00  
Spot: N2SWSW Sec/Twnshp/Rge: 27-23S-4W  
990 feet from S Section Line, 520 feet from W Section Line  
Lease Name: HILL Well #: 4  
County: RENO Total Vertical Depth: 3430 feet

Operator License No.: 5118  
Op Name: TGT PETROLEUM CORPORATION  
Address: 7570 W 21ST ST N STE1010D PO BOX 7  
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	664		100 SX
COND	10.75	227		275 SX
PROD	4.5	3427		100 SX

111.48

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 938-2388

Proposed Plugging Method: PER KCC RULES

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/03/2009 11:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

4/1/2009 CUT OFF HEAD CEMENT AT SURFACE BETWEEN CONDUCTOR AND SURFACE PIPING, SANDED BACK TO 3270' PLACED 4 SX OF CEMENT ON TOP OF SAND. RIPPED OFF CASING AT 1504' PULLED CASING, RAN BACK IN WITH 736' OF 2 3/8" TUBING, SPOTTED 50 SX OF COMMON CEMENT W/3% CC. 4/2/09 TAGGED 736' FOOT PLUG AT 615', RAN TUBING INTO 288' SPOTTED 150 SX OF COMMON CEMENT WITH 200 LBS OF HULLS AND 3% CC. 4 HOURS LATER TAGGED CEMENT TOP AT 256', RAN TUBING IN SPOTTED 125 SX OF 60/40/4% GEL, W/3% CC, 2 HOURS LATER TAGGED TOP OF CEMENT AT 224', RAN IN TUBING TO 224' CIRCUALTED TO SURFACE WITH 150 SX OF 60/40/4% GEL AND 3% CC, FILLED CELLAR WITH CEMENT. 4/3/2009 CHECKED TOP PLUG, CELLAR STILL FULL, OK TO CLOSE.

Perfs:

Top	Bot	Thru	Comments
3331	3336		

INVOICED  
DATE 5-6-09  
INV. NO. 2009061519

KANSAS CORPORATION COMMISSION  
APR 16 2009  
RECEIVED

Remarks: QUALITY OILWELL CEMENTING INC. TICKET #2344

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

*B. J. Hope*

(TECHNICIAN)

JK

PRT