

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-20194-00-00  
Spot: NESENE Sec/Twnshp/Rge: 22-23S-4W  
3650 feet from S Section Line, 330 feet from E Section Line  
Lease Name: MILLER A Well #: 5  
County: RENO Total Vertical Depth: 3664 feet

Operator License No.: 5118  
Op Name: TGT PETROLEUM CORPORATION  
Address: 7570 W 21ST ST N STE1010D PO BOX 7  
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	614		100 SX
COND	10.75	218		210
PROD	5.5	3664		125 SX

119.08

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/26/2009 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 938-2388

Proposed Plugging Method: PER KCC RULES

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/31/2009 6:30 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

3/26/2009 SANDED BACK TO 3080' TOP WITH 5 SX OF CEMENT. RIPPED OFF CASING AT 1810' PULLED CASING TO 672' SPOTTED 50 SX OF CLASS A COMMON CEMENT WITH 3% CC. WELD NIPPLE ON CONDUCTOR PIPE PUMPED 50 SX DOWN BACKSIDE COMMON CEMENT W 3% CC. 3/31/2009 TAGGED WITH WIRELINE, -432' PLUG FELL TO 800 PLUS FEET, COULD NOT GET 5.5 CASING PAST 410', RAN BACK IN WITH 2 3/8 TUBING TO 440' SPOTTED 100 SX CLASS A COMMON CEMENT W/ 3% CC AND 300 LBS OF COTTON SEED HULLS. TAGGED AT 150' 3 HOURS LATER. CIRCULATED TO SURFACE WITH 70 SX OF CEMENT 60/40 4% GEL POS MIX WITH 3% CC. PLACED AN ADDITIONAL 3SX OF CEMENT DOWN BACKSIDE OF 8 5/8. 4/1/2009 CHECKED TOP PLUG, OK AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
3364	3368	CSG	
3352	3358	CSG	

INVOICED  
DATE 5-6-09  
INV. NO. 2009061519

KANSAS CORPORATION COMMISSION

APR 16 2009

RECEIVED

Remarks: USING QUALITY OILWELL CEMENTING INC. TICKET #2342

Plugged through: TBG

District: 02

Signed

B. J. Hope

(TECHNICIAN)