

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20210-00-00
Spot: NESWNWNW Sec/Twnshp/Rge: 22-23S-4W
840 feet from N Section Line, 580 feet from W Section Line
Lease Name: SABIN A Well #: 2
County: RENO Total Vertical Depth: 3355 feet

Operator License No.: 5118
Op Name: TGT PETROLEUM CORPORATION
Address: 7570 W 21ST ST N STE1010D PO BOX 7
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	640		100 SX
COND	13.38	237		250 SX
PROD	5.5	3347	2430	75 SX

109.04

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/25/2009 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 938-2388

Proposed Plugging Method: PER KCC RULES AND REGULATIONS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/25/2009 2:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

3/24/2009 CUT OFF HEAD CHECKED FOR CEMENT BETWEEN CONDUCTOR AND SURFACE PIPE CEMENT AT SURFACE. SANDED BACK TO 3270' TAGGED AND 5 SX OF CEMENT PLACED ON TOP OF SAND 3/25/2009-SPOTTED 50 SX OF CLASS A CEMENT WITH 3% CC. WAITED 2.5 HOURS TAGGED PLUG AT 440', PULLED CASING TO 275' CIRCULATED TO SURFACE WITH 125 SX OF CLASS A CEMENT WITH 3% CC. CHECKED TOP PLUG ON 3/26/2009 OK, STILL FULL.

Perfs:

Top	Bot	Thru	Comments
3334	3338	CSG	

AVO GED
5-6-09
W. NO 2009061519
RECEIVED
APR 21 2009
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING INC. TICKET #2338 - COMMON CLASS A CEMENT WITH 3% C.C.

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

SK

PKT