

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21404-00-00
Spot: NWNE Sec/Twnshp/Rge: 30-32S-15W
4805 feet from S Section Line, 1943 feet from E Section Line
Lease Name: BRASS Well #: 1
County: BARBER Total Vertical Depth: 4865 feet

Operator License No.: 0
Op Name: LANDOWNER
Address:

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4720		WITH 2 SX CMT
COND	16	73		WITH 10 SX CMT
PROD	5.5	4839	2400	WITH 125 SX CMT
SURF	8.625	422		WITH 300 SX CMT

Well Type: GAS UIC Docket No: Date/Time to Plug: 04/03/2009 9:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4720' & 2 SX CMT. PLUG AT 840' WITH 15 SX GEL & 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/03/2009 10:50 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4720' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN CSG & RUN 2 3/8" TBG IN TO PLUG THROUGH. 1ST PLUG AT 840' WITH 15 SX GEL & 50 SX CMT W/50# HULLS. 2ND PLUG AT 450' WITH 50 SX CMT W/50# HULLS. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4772	4778		

INVOICED
DATE: 5-7-09
INV. NO. 2009061521

RECEIVED
APR 22 2009

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

APR - 8 2009

KCC DODGE CITY

Signed

Stephen J. Pfeifer
(TECHNICIAN)

Form CP-100